

Banner appropriate to article type will appear here in typeset article

Lift-anchored predictive coefficient states for wall-pressure estimation of extreme vortex-gust airfoil encounters

Alberto Solera-Rico^{1,2}, Arnau Miró^{3,4}, Oriol Lehmkuhl⁴ and Carlos Sanmiguel Vila^{1,2}

¹Aerial Platforms Department, Spanish National Institute for Aerospace Technology (INTA), San Martín de la Vega, 28330, Madrid, Spain

²Department of Aerospace Engineering, Universidad Carlos III de Madrid, Leganés, 28911, Madrid, Spain

³TUAREG Research Group, Universitat Politècnica de Catalunya (UPC), Carrer Colom 11, 08222 Terrassa, Spain

⁴Barcelona Supercomputing Centre (BSC), CASE Large-Scale Computational Fluid Dynamics, Plaça d'Eusebi Güell, 1-3, 08034 Barcelona, Spain

Corresponding author: Carlos Sanmiguel Vila, csanvil@inta.es

(Received xx; revised xx; accepted xx)

Extreme vortex-gust encounters of a post-stall airfoil are wake-reorganisation events: the transient load is the surface signature of leading-edge-vortex roll-up and shedding, and the release parameters alone do not fix the wake once the gust has passed. We treat the encounter as a state-estimation problem, and ask what it takes to build, compress, advance and recover a reduced coefficient state from the only sensors a wing carries, its wall pressure. Using direct numerical simulations of a NACA 0012 airfoil at $\alpha = 14^\circ$ and $Re = 5000$, perturbed by Taylor vortices spanning gust strength, core diameter and offset, a supervision cube over three aerodynamic heads shows that a scalar lift anchor is load-bearing for predictive latent health, a physics-constructed near-body force-element head sharpens the peak loads on top of it (peak-region R^2 of 0.86 over three seeds), and a wake head carries the wake state. Lift information is dimension-invariant down to four coefficients, where it is linearly accessible; the wake state is not compressible below sixteen. A direct multi-horizon quantile forecaster advances the state where autoregressive rollout compounds, and knowing the true gust parameters degrades the forecast. A leakage-free ensemble filter family sensing eight taps then tracks the loads through the encounter, phase-resolved and in physical units: a knob-free two-stage filter reaches an impact-phase analysis R^2 of 0.794 in distribution and 0.837 at the strongest held-out gusts with no divergences, innovation-consistency calibration of the forecast-derived noise is refuted in favour of a model-error reading, and the predictive states remain uniformly estimatable across the dimension axis where the reconstructive geometry fails unpredictably with dimension and training seed. The wake enstrophy stays beyond any wall-limited filter of this flow, a bound set by the sensing geometry rather than the state.

Key words: vortex shedding, low-dimensional models, machine learning

1. Introduction

Small uncrewed aerial vehicles are increasingly expected to operate in environments where the incoming flow is neither steady nor weakly disturbed. Urban canyons, mountainous terrain, coastal regions and ship or building wakes can expose these vehicles to gusts whose characteristic length scale is comparable to the wing chord and whose velocity is of the same order as the flight speed (Jones *et al.* 2022; Mohamed *et al.* 2023; Fukami & Taira 2023). In this regime, gusts cannot be treated as small perturbations of an otherwise steady aerodynamic state. They interact with separation, vortex shedding and wake recovery, producing large transient loads and rapid changes in the surrounding flow organisation. For small vehicles, this coupling directly affects navigability, control authority and flight safety.

This regime has motivated a growing body of work on extreme aerodynamics (Taira 2026). A canonical example is the interaction between a discrete vortex gust and a wing or airfoil, where the disturbance has sufficient strength to reorganise the near wake rather than merely modulate the instantaneous force (Fukami *et al.* 2025). Recent studies have shown that apparently complex gust encounters can exhibit unexpectedly low-dimensional structure when viewed in suitable coordinates. Lift-augmented autoencoders have revealed compact manifolds for extreme vortex-gust airfoil interactions (Fukami & Taira 2023), and the same reduced description has been used to support phase-amplitude analysis and data-driven transient lift attenuation (Fukami *et al.* 2024). Related work has also shown that large-scale vortical structures can display similarities across laminar and turbulent extreme-gust encounters (Odaka *et al.* 2026). These results suggest that the dynamical organisation of extreme aerodynamic flows may be simpler than the full flow-field dimension implies.

For practical deployment, however, compactness alone is not sufficient. A reduced description intended for gust mitigation must be usable as a plant state: it must be estimated from available sensors, advanced in time by a predictive model and queried by a controller or decision algorithm (Loiseau *et al.* 2018). This requirement places the problem closer to state estimation and model-based control than to flow-field compression alone. Surface pressure is especially important in this context, because it is one of the few measurements that can be obtained at high bandwidth on an aerodynamic body. Recent gust-modelling studies have therefore used sparse surface-pressure histories to infer unsteady aerodynamic loads and, more broadly, to bridge spatial pressure correlations and temporal flow memory (Zhong *et al.* 2023; Haughn *et al.* 2024; Chen *et al.* 2026), and Bayesian sequential estimation has begun to close the loop between sparse pressure and low-order aerodynamic states, with uncertainty carried alongside the estimate (Mousavi & Eldredge 2025; Eldredge & Mousavi 2025). Such approaches indicate a path towards deployable gust-response models, but they also sharpen the central question: what reduced state should be estimated from the wall in the first place?

Most current nonlinear reduced-order models for extreme aerodynamic flows are built around reconstruction-trained autoencoders. In this approach, a convolutional encoder maps the flow field to a low-dimensional latent vector, and a decoder reconstructs the original field. Aerodynamic observables, such as lift, can be added as auxiliary losses to orient the latent space towards physically relevant quantities (Fukami & Taira 2023, 2025). This strategy is powerful because it preserves a direct connection between the latent variables and the resolved flow. It also provides a natural route to visualisation and

interpretation, since the decoder maps latent coordinates back to physical space. Similar ideas have been combined with variational autoencoders and sequence models to build predictive reduced-order models of chaotic flows (Solera-Rico *et al.* 2024; Fukagata & Fukami 2025).

Yet a reconstruction-trained latent space is not necessarily the best space for prediction. The decoder encourages the encoder to preserve information needed to reproduce the instantaneous field, but the time-advancing model requires coordinates that remain stable and informative under autoregressive rollout. These two requirements need not coincide. Recent comparisons in controlled wake flows indicate that convolutional-autoencoder-based predictors can be more prone to long-horizon divergence, whereas POD-based predictors, despite their linear and less compact representation, may retain higher median forecast accuracy and a narrower spread (Solera-Rico *et al.* 2025). This does not make POD preferable as a general representation of nonlinear separated flows. Rather, it exposes a tension: nonlinear encoders can compress more aggressively, but reconstruction compactness does not guarantee forecast robustness. The question is therefore whether one can construct nonlinear reduced states that retain the compactness of learned manifolds while improving their predictive usability.

This question motivates the use of a joint-embedding predictive architecture (JEPA) (LeCun 2022). In contrast with an autoencoder, a JEPA does not train the representation by reconstructing the input field. Instead, it learns an encoder and a predictor such that the present latent state predicts a future latent state. In computer vision, image- and video-based JEPAs have been introduced as non-generative self-supervised models that predict in representation space rather than pixel space (Assran *et al.* 2023, 2025). For the present fluid-mechanics problem, the relevance of JEPA is more specific: it provides a way to train the reduced coordinates in the same space in which the forward model will later operate. The architecture is therefore used here as a diagnostic tool to test whether predictive training can produce a nonlinear state that is more stable under rollout than a reconstruction-trained latent.

This choice creates a second question. Because the JEPA state is trained without a decoder, it is not obvious what physical information is retained by its coordinates. A low forecast error in latent space would be insufficient if the state did not carry the wake variables that matter for gust response. We therefore treat decoding not as part of the training objective, but as an a-posteriori diagnostic. After training the reduced state, we ask what can be recovered from it: aerodynamic observables, wake enstrophy, flow-field structures and, ultimately, the latent coordinates themselves from sparse wall pressure. This separation between predictive training and diagnostic decoding allows us to distinguish three properties that are often conflated: whether a state is compact, whether it is physically readable and whether it remains usable when advanced by its own dynamics.

The present work examines these questions using a canonical post-stall vortex-gust interaction. The gust parameters are not supplied to the predictive model; the encoder receives only the instantaneous flow state, and the predictor advances the latent state from its own history. We compare a predictive joint-embedding model with reconstruction-trained nonlinear encoders and a linear POD representation at matched latent dimension. The comparison is not designed to identify the method that reconstructs the vorticity field most accurately. Instead, it asks which representation supplies a reduced aerodynamic state that can be forecast, decoded and estimated in a form relevant to future gust-mitigation systems.

The paper makes four contributions, one per stage of the estimation problem. First, we settle what constructs the state: a supervision cube over three aerodynamic heads, three seeds per cell under pre-registered gates, shows that a scalar lift anchor is load-bearing for

predictive latent health, that a near-body force-element head constructed from the Chang decomposition sharpens the peak loads on top of it, and that the wake head carries the wake state; the division of labour replaces the single wake-supervision attribution of our earlier framing. Second, we give the compression its honest form: lift information is dimension-invariant and linearly accessible at four coefficients while the wake state is distributed and needs sixteen, a two-tier statement in which linear-probe readability is a readout property, not an information property. Third, we make the family forecast comparison operator-robust with one direct multi-horizon forecaster trained identically on every latent, and show that autoregressive compounding, not the state, is the rollout failure mode, and that conditioning on the true gust parameters degrades the forecast. Fourth, we demonstrate the state in a leakage-free sequential filter family, leakage-free meaning that the quantities the paper scores, the lift and wake probes, can never enter the filter’s innovation, which senses only wall pressure; we evaluate it phase-resolved and in physical units across the gust-intensity envelope, attribute its impact-side under-dispersion to calibration and fix it with a forecast-derived state-dependent noise, attribute its relaxation error to forecast contraction and address that with a fixed-lag smoother, and show the predictive states uniformly wall-estimatable across the dimension axis where the reconstructive geometry fails unpredictably. We are explicit about the limits: the best filter’s in-distribution impact median does not beat a static delay-embedded inverse, whose case fails instead in the tails and at the $|G| = 4$ boundary; the wake enstrophy remains beyond any wall-limited filter of this flow; and the mid-plane representation reaches a three-dimensional observability boundary at the strongest gusts. This study investigates a fluid-mechanics question through a learning architecture: what kind of reduced state can carry the wake dynamics of an extreme gust encounter while remaining estimatable from the wall and predictive enough to serve as a future plant model?

2. Flow configuration and data

2.1. Vortex gust-airfoil interaction

We study a NACA 0012 airfoil at angle of attack $\alpha = 14^\circ$ and chord Reynolds number $Re = 5000$, perturbed by a discrete vortex gust modelled as a spanwise-oriented Taylor vortex released upstream of the leading edge. The data analysed here are our own direct numerical simulations of this configuration, computed with the GPU-enabled spectral-element solver SOD2D (Gasparino *et al.* 2024) with no subgrid-scale model, so that all scales of the separated wake are resolved at this Reynolds number. The solver is run in the low-Mach regime in which the flow is effectively incompressible. The configuration and its physical characterisation follow Fukami, Smith & Taira (2025), which is the reference for the physics, not the source of the data. The vortex has the azimuthal velocity profile

$$u_\theta(r) = u_{\theta,\max} \frac{r}{R} \exp\left[\frac{1}{2}\left(1 - \frac{r^2}{R^2}\right)\right], \quad (2.1)$$

which peaks at the core radius $r = R$ (Taylor 1918), and is parametrised by three scalars: the signed gust ratio $G \equiv u_{\theta,\max}/u_\infty$, the core diameter $D \equiv 2R/c$, and the wall-normal offset Y of the vortex centre, the displacement normal to the chord (the laboratory coordinates are rotated by the angle of attack to define Y). The released-data case identifiers encode the solver’s opposite sign convention, $s = -G$, so a case labelled G+4.00 in the archive corresponds to $G = -4$ here. The profile and the (G, D, Y) sampling follow the configuration of Fukami *et al.* (2025). The training envelope spans $|G| \in \{0.5, 1.0, 1.5, 2.0, 3.0\}$ with $G = 0$ as the undisturbed reference, $D \in \{0.5, 1.0, 1.5\}$

chords, and $Y \in [-0.4, +0.4]$; the value $|G| = 4$ is held out as an extrapolation boundary, for reasons that are physical and that we return to below. Convective time t is measured in chords and set to zero when the vortex centre reaches the leading edge.

Without a gust, the $\alpha = 14^\circ$ wake at this Reynolds number is massively separated and sheds periodically; in dynamical terms the undisturbed flow is a limit cycle. A gust encounter is then a transient excursion from this limit cycle and back, and it is helpful to read it in stages (figure 1) (Smith *et al.* 2024; Fukami *et al.* 2025; Odaka *et al.* 2026). The vortex first induces a strong wall-normal vorticity flux at the leading edge, the airfoil experiences a sharp lift excursion as a leading-edge vortex (LEV) forms, the LEV rolls up and sheds together with a trailing-edge structure as the load reaches its extremum, and the wake then relaxes back toward the baseline shedding. The sign of G sets whether the first lift excursion is positive or negative, Y sets the side and strength of the impingement, D sets how much of the encounter is dominated by the vortex core, and the impact timing sets the phase of the baseline cycle at which the disturbance arrives. The five observables defined in §2.2 are quantitative summaries of exactly this sequence.

A consequence of the source characterisation (Fukami *et al.* 2025) is central to how we read the extrapolation case. For $|G| \leq 3$ the encounter is primarily two-dimensional, so a mid-plane slice of the spanwise vorticity carries the relevant large-scale dynamics; for $|G| \geq 4$ the interaction becomes genuinely three-dimensional, with fine-scale instabilities developing during impact. We confirm this from the full three-dimensional vorticity fields: the fraction of the spanwise-vorticity (ω_z) enstrophy not captured by its spanwise mean, the content a mid-plane slice discards, is roughly constant across the training range ($|G| \leq 3$, post-impact wake median ≈ 0.20) and rises about threefold at $|G| = 4$ (≈ 0.56 , over the four available cases). Because the encoder in this work consumes a single mid-plane vorticity field (§2.2), the held-out $|G| = 4$ case is not merely one parameter step beyond the training range; it is a regime in which the quantity the encoder observes no longer determines the true dynamics. We therefore treat $|G| = 4$ as a physical observability boundary rather than as a claim of parametric generalisation.

2.2. Data, fields, and observables

Each simulation case is one long run partitioned into encounters of 120 cached frames at $\Delta t = 0.05 t/c$, one encounter per gust release. The simulations use a spectral-element discretisation of polynomial order $p = 4$, and the fields are cached on a structured grid of $192 \times 96 \times 32$ points spanning $x/c \in [-1.5, 4.5]$ and $y/c \in [-1.5, 1.5]$ with a spanwise extent of approximately one chord; this analysis subdomain matches the data-driven subdomain of the source characterisation (Fukami *et al.* 2025). The lift and drag coefficients are $C_L = F_L / (\frac{1}{2} \rho u_\infty^2 c)$ and $C_D = F_D / (\frac{1}{2} \rho u_\infty^2 c)$, obtained by integrating the pressure and viscous stresses over the airfoil surface. The remaining DNS solver-resolution details required for full reproducibility, the free-stream Mach number, the domain and spanwise extent, the element and solution-point counts, the near-wall spacing, the time step and CFL, the gust-release station, and the grid and time-step sensitivity, are listed as an author-fill checklist in table 1. The dataset comprises 102 cases partitioned into training, validation (the held-out encounters of the training cases, denoted test_a), an in-distribution test set (test_b), and an out-of-distribution test set (test_c). The in-distribution test set is stratified to span the gust strengths, the three core diameters, and the two source groups (figure 2); test_c is the $|G| = 4$ extrapolation set, sampled symmetrically in both signs of the gust (§2.2). These 102 cases are separated in preprocessing into 450 encounter windows of 120 frames each, one per gust release: 268 training, 100 validation (test_a, the held-out last encounters of the training cases), 42 test_b, and 40 test_c. The undisturbed reference case is retained in training. Behind these encounter counts are far fewer distinct cases:




Figure 1. The vortex gust as a wake-reorganisation event, shown as a gust-strength sweep at fixed core diameter $D = 0.5$ and wall-normal offset $Y = -0.1$ (the first encounter of each case). (a) The lift coefficient C_L against convective time t/c for the four cases, with $t/c = 0$ the gust-release instant and impact near $t/c = 2$; the undisturbed baseline ($G = 0$) is grey, and the load excursion deepens and widens monotonically with the gust strength $|G|$. (b) The mid-plane spanwise vorticity ω_z for each case (rows, $G = 0, -0.5, -1.5, -4$) at four convective times (columns, $t/c = 1, 2, 3, 4$), in raw physical units with the colourbar clipped at ± 3 (the intense cores saturate; the wake structure away from them lies within the range), and the airfoil drawn as a filled polygon. The strong gust injects a vortex that reorganises the wake through impact, while the weak cases perturb the baseline shedding only slightly; $G = -4$ is the $|G| = 4$ extrapolation case, shown here only as a physical illustration. The load spike and the wake reorganisation are the surface and field signatures of the same event, and the release parameters alone do not fix where the wake sits afterwards, which is why the wake, not only C_L , is the endpoint a reduced state must carry.

Quantity	Value	Why a referee needs it
Free-stream Mach number (or incompressible-limit confirmation)	[PENDING:]	Confirms the low-Mach formulation is effectively incompressible at $Re = 5000$.
Computational domain and spanwise extent L_z/c	[PENDING:]	Bounds domain blockage and confirms the span resolves the three-dimensional wake.
Element and solution-point counts	[PENDING:]	Fixes the spatial resolution of the spectral-element discretisation.
Minimum wall-normal spacing $\Delta n_{\min}/c$ and wall units Δn^+	[PENDING:]	Shows the near-wall layer is resolved without a wall model.
Time step $\Delta t u_\infty/c$ and maximum CFL	[PENDING:]	Establishes the temporal resolution and stability of the integration.
Gust-release station x_0/c	[PENDING:]	Sets the upstream distance over which the Taylor vortex develops before impact.
Grid and time-step sensitivity check (baseline and a representative gust case)	[PENDING:]	Demonstrates that the reported statistics are converged.

Table 1. DNS solver-resolution details required for full reproducibility (§2.2). The simulations are performed with SOD2D without a subgrid-scale model; the solver-resolution metadata required to substantiate the DNS designation are listed here and will be supplied before submission. Values marked pending are owned by the simulation collaborators and are filled from `paper/dns_metadata.yaml` before submission.

the 42 test_b encounters come from only 10 held-out cases (6 interior and 4 boundary tier) and the 40 test_c encounters from 8 cases, with most cases contributing four to six encounters that share a baseline shedding history. Encounters of the same case are therefore not independent, so encounter-level intervals overstate the effective sample size; the headline comparisons are reported additionally with a case-clustered bootstrap and a case-level paired test (Appendix A). The partition is fixed once and used identically by every model and baseline.

The $|G| = 4$ extrapolation boundary is sampled symmetrically by combining the periodic archive cases with four additionally released cases at the opposite sign of the gust. We verified the additional cases against the archive by a physical consistency check on the load rather than by trusting the file metadata: at matched core diameter and offset, the two signs of the $|G| = 4$ gust produce near mirror-image lift transients, one a positive-first excursion peaking near $+8.3$ and the other troughing near -7.6 , as the sign of the gust ratio sets the sign of the first excursion (§2.1). This confirms that the two halves of the symmetric boundary set are physically consistent and that the sign-asymmetry analysis of the operating envelope (§4.8) is sound. Sampling the boundary at both signs is a genuine improvement over a one-sided $|G| = 4$ set: it lets the sign asymmetry be measured rather than assumed.

For each frame the cache stores the mid-plane spanwise vorticity $\omega_z(192, 96)$, the span-averaged wall pressure $p_{\text{wall}}(192)$, and the lift and drag coefficients C_L, C_D . The vorticity is normalised by a fixed pipeline: a spatial mask removes the solid and one adjacent cell layer to suppress the leading-edge finite-difference artefact, a per-encounter high-percentile clip caps spikes, and the field is scaled by three times the training standard deviation ($\sigma_{\text{train}} = 3.5396$) with no mean shift, preserving the vorticity antisymmetry. All representation and probe losses are computed in this normalised space; unnormalised values are used only for physical-units metrics and figures. The field-reconstruction similarity reported below uses the structural similarity index of Wang *et al.* (2004) with the standard constants $K_1 = 0.01$, $K_2 = 0.03$ and a dataset-dependent dynamic range $L = 8.487$, set to twice the global

99.9th percentile of the normalised target magnitude over the validation split so that the index is comparable across reruns. Appendix A repeats the primary wake probe under no amplitude clip and under a single training-pooled leak-free threshold (established on the previous-generation encoders; the pipeline is unchanged in this revision), and the family ordering is unchanged, so the per-encounter clip does not drive the result.

We evaluate forward closure against five physical observables that together span body-force and spatially distributed wake diagnostics. The lift and drag coefficients C_L and C_D are the body forces. The wake enstrophy and the positive and negative circulation are spatially distributed wake observables: they integrate (signed) vorticity over the wake region and are the most demanding to forecast, because they are sensitive to the redistribution of vorticity that the LEV roll-up and shedding produce. The choice is deliberate: the wake observables can change sharply while the scalar forces change little, so they are the part of the encounter most likely to separate a representation that has captured the gust-vortex physics from one that has only captured its force signature. On these grounds we fix two co-primary endpoints in advance: the wake enstrophy, which the reduced state must carry beyond the release parameters, and the lift coefficient C_L , which the sequential wall-pressure estimator of §3.3 tracks and in which the operating envelope is stated. The remaining three observables are reported as secondary and descriptive. This pre-registration is what the family-wide multiplicity correction in Appendix A is applied against.

The five observables are defined on each frame of the masked vorticity field ω_z described above. The lift and drag coefficients C_L, C_D are as defined earlier in this section. On the wake window $\Omega_w = \{(x, y) : x/c \in [0.5, 4], |y/c| \leq 1\}$ the wake enstrophy is

$$E_w(t) = \int_{\Omega_w} \omega_z^2 dA, \quad (2.2)$$

and the signed wake circulations integrate the vorticity over its strongly rotational parts,

$$\Gamma^+(t) = \int_{\Omega_w, \omega_z > \omega_c} \omega_z dA, \quad \Gamma^-(t) = \int_{\Omega_w, \omega_z < -\omega_c} \omega_z dA, \quad (2.3)$$

with threshold $\omega_c = 1$ in the cleaned vorticity units. The signed circulations at $\omega_c \in \{0.5, 1, 2\}$ are nearly collinear (pairwise Pearson well above 0.9 across held-out frames) and the predictive latent’s circulation closure advantage over the reconstructive baseline is essentially unchanged across them, so the closure does not depend on this threshold. Every case uses the same fixed window and mask, and values are reported in the cache vorticity units integrated over chord-normalised area. The forecast horizon $H = 16$ is the sixteenth cached frame after impact, $t = 16 \Delta t = 0.8 c/u_\infty$.

One definitional point bounds how these observables are read. The wake and flow observables (the enstrophy and the two circulations) are computed on the same mid-plane slice the encoder consumes, so they omit the out-of-plane content quantified in §2.1 (roughly a fifth of the ω_z enstrophy in distribution), whereas C_L and C_D are true three-dimensional surface-integrated forces. The closure therefore compares mid-plane wake diagnostics against three-dimensional forces, and the mid-plane proxy is weakest at the $|G| = 4$ extrapolation boundary, where the out-of-plane fraction rises substantially.

3. Predictive latent representation and evaluation protocol

3.1. Model and training objective

The model takes no gust parameters: neither the encoder nor the predictor receives (G, D, Y) . The predictive encoder E_θ maps the mid-plane vorticity field $\omega_z(192, 96)$ to a




Figure 2. Parameter-space sampling of the 102 cases in the (G, D, Y) gust envelope, shown as three two-dimensional projections and coloured by split: training (268 encounters), the stratified in-distribution test set (test_b, 42 encounters from 10 cases, split into interior and boundary tiers), and the out-of-distribution extrapolation set (test_c, 40 encounters from 8 cases). The dashed lines mark the $|G| = 4$ extrapolation boundary, now sampled at both signs of the gust so that the boundary set is symmetric rather than one-sided. Training mass concentrates near $Y/c = 0$, which is why the wall-normal offset is the least well resolved parameter (§4.10).

latent $\mathbf{z} \in \mathbb{R}^d$ at the headline dimension $d = 32$. It is a hybrid network: three convolutional downsampling stages produce a $24 \times 12 \times 256$ feature map, a six-layer vision transformer processes the resulting tokens, and the class-token output is projected to $\mathbf{z}$ through a single linear layer with a batch-normalisation boundary, which the characteristic-function regulariser below requires. The encoder is therefore a pure state map, and this is the property that lets the latent itself serve as the observable a controller would have access to, since at deployment the gust parameters are not known a priori (§5).

The predictor P_ϕ advances the pooled state in time, from its own history alone, so the model is unconditioned end to end. It is a vector sequence model: a six-layer autoregressive transformer with rotary temporal positions and a causal mask that maps a short history of 32-vectors to the next 32-vector, with no gust input. From the two most recent encoded states it rolls eight steps open loop, feeding its own predictions back in, and the loss is the multi-step error between the rolled coefficients and the online encoder outputs at the matching frames, detached. The pipeline is therefore as plain as a linear or autoencoder reduced-order model: 32 numbers in, a dynamics model on the vector, 32 numbers out, with no spatial map anywhere in the loop. The state is the pooled vector at every stage: the anti-collapse regulariser, the observable heads, the probes, and the estimator all read the same 32-vector, and nothing in the model carries more. The estimator of §3.3 refits a predictor of this same class on the frozen pooled trajectories for its forecast step, so the training and estimation dynamics share a function class. Internal structure for both is given in Appendix A. Figure 4(a) shows the encoder and predictor, and panel (b) sets out the matched-predictor evaluation protocol used throughout; the contrast between the predictive training signal and the reconstructive one, in which the reconstructive autoencoder passes the field at time t through an encoder and a decoder and incurs a field-space error whereas the predictive model encodes the fields at t and $t + \Delta t$ with shared weights and incurs a latent-space error between the predicted and observed target embeddings, with no field-space loss, is drawn in Appendix A (figure 22). Table 2 summarises the two networks.

The predictive encoder and predictor are trained jointly on a multi-step open-loop rollout term, the predictor rolled eight steps from its own outputs with no teacher forcing against

Table 2. Encoder and training-predictor configuration, counted from the released $d = 32$ checkpoint. The model is unconditional: no gust parameters $\mathbf{c} = (G, D, Y)$ enter the encoder or the predictor. Two small auxiliary heads read observables off the encoder output during training (a lift head and an 80-dimensional wake-spectrum head; §3.1). The estimation-stage forecast model of §3.3 is a predictor of the same class refitted on the frozen pooled trajectories.

	Encoder E_θ	Predictor P_ϕ
role	field $\rightarrow$ pooled state (unconditional)	pooled-state rollout (unconditional)
input	$\omega_z \in \mathbb{R}^{192 \times 96}$	pooled states $\mathbf{z} \in \mathbb{R}^{32}$
backbone	3 conv. stages + 6-layer ViT	6-layer causal transformer (RoPE)
width / heads	256 / 8	384 / 16
image tokens / context	$24 \times 12 = 288$	2 frames, rolled 8 steps open loop
conditioning	none	none
state read-out	class token $\rightarrow$ linear $\rightarrow$ BatchNorm	next pooled state
parameters	6.7M	10.7M

detached online targets, and an anti-collapse regulariser that prevents the encoder from collapsing to a constant. We use the characteristic-function regulariser of Balestrierio & LeCun (2025); Maes *et al.* (2026), which matches the latent distribution to an isotropic Gaussian through a small number of random projections, with an automatic fall-back to a variance-covariance objective (Bardes *et al.* 2022) should the participation ratio of the latent indicate collapse. Its configuration is given in Appendix A.

Three auxiliary heads read aerodynamic observables off the encoder output during training: a lift head that maps $\mathbf{z}_t$ to $C_L(t)$, a wake head that maps $\mathbf{z}_t$ to an 80-dimensional signed wake spectrum, and a near-body head, constructed in §3.1.1 below, that maps $\mathbf{z}_t$ to an 80-dimensional lift-element observable of byte-matched capacity. All are trained with small weights jointly with the representation and none is part of the latent-prediction loss. The scalar-lift lineage is the observable augmentation of Fukami & Taira (2023, 2025); which head buys which property of the state is the subject of the conditioning study of §4.1. The wake target itself is a fixed descriptor chosen by design rather than tuned: it pairs a coarse signed spatial pooling of the wake region, which retains the layout of the alternating positive and negative vortices while discarding pixel-level detail, the spatial-pyramid construction of Lazebnik *et al.* (2006), with a radially-averaged power spectrum, the canonical isotropic scale descriptor of a turbulent field (Pope 2001) and an established compact image descriptor in machine learning (Durall *et al.* 2020), so it encodes both where the wake vortices sit and at which scales their energy resides. Pairing a localised spatial summary with a multiscale spectral one is the spatial-plus-scale representation formalised by the wavelet scattering transform (Bruna & Mallat 2013), which has been applied to turbulent flow fields precisely to recover geometry that the power spectrum alone cannot resolve (Skinner *et al.* 2025). We keep the descriptor compact, at 80 dimensions, so that it constrains the wake structure without over-parameterising the target on the available training encounters. The head-supervision axis is no longer a confound: the $2 \times 2 \times 2$ conditioning cube of §4.1, three seeds per cell with matched reconstructive anchors, isolates each head’s contribution under pre-registered gates.

3.1.1. The near-body lift-element head

The third supervision head targets a physically constructed near-body observable built on the force-element decomposition of Chang (Proc. R. Soc. Lond. A 437, 1992), in the form popularised for vortex-dominated flows by Menon and Mittal (J. Fluid Mech. 918, 2021).

auxiliary potential ϕ_L (Chang 1992), Neumann BC on the body




Figure 3. The Chang auxiliary potential ϕ_L of equation (3.1) on the cache grid (contours), the feathered $\delta_n = 0.3c$ supervision band (dashed) and the airfoil footprint; the inset shows the lift direction $\mathbf{e}_L$ against the inclined freestream at $\alpha = 14^\circ$.

An auxiliary potential ϕ_L is defined by the exterior boundary-value problem

$$\nabla^2 \phi_L = 0 \text{ outside the body,} \quad -\mathbf{n} \cdot \nabla \phi_L = \mathbf{n} \cdot \mathbf{e}_L \text{ on the body,} \quad \phi_L \rightarrow 0 \text{ far away,} \quad (3.1)$$

with $\mathbf{e}_L = (-\sin \alpha, \cos \alpha)$ the lift direction at $\alpha = 14^\circ$. Equation (3.1) is discretised once on the 192×96 cache grid with a staircase immersed Neumann condition on the solid-adjacent cell faces and a homogeneous Dirichlet far field, and solved directly (figure 3); the interior Laplacian residual of the stored solution is 6.4×10^{-13} in the maximum norm. The lift-element density is then the pointwise field

$$e(\mathbf{x}, t) = \omega_z (-v \partial_x \phi_L + u \partial_y \phi_L), \quad (3.2)$$

evaluated from the raw mid-plane velocity and vorticity with the stored sign convention verified empirically (the cache stores $\partial u / \partial y - \partial v / \partial x$, so the standard ω_z is its negation). Because the cache window truncates the domain, the full-domain integral of (3.2) does not track the lift; the band-restricted field does, and the head therefore supervises e inside a feathered near-body band $w(\mathbf{x}) = \max\{0, 1 - \delta(\mathbf{x})/0.3c\}$, with δ the Euclidean distance to the body and its adjacent cells. The banded field $w e$, scaled by a fixed constant chosen so its 99th percentile magnitude is order one, is compressed to an 80-dimensional target by exactly the wake-observable construction: 64 sign-preserving patch energies (an 8×4 grid of $\log(1 + \text{relu}(\pm x)^2)$ pooled energies) concatenated with a 16-bin Hann-windowed radial power spectrum. The two 80-dimensional targets are byte-matched in capacity, and the wake and near-body heads share one network class, so the conditioning comparison of §4.1 isolates the supervision signal, not the head architecture. A precompute quality gate requires the median lagged correlation between the band-integrated element and the stored lift over the gust-bearing training encounters (lag search $|\ell| \leq 25$ frames) to exceed 0.4; the achieved value is 0.74. The principled weighting is not interchangeable with a plain vorticity-magnitude proxy: the patch-block cosine between the two targets is 0.68 on the comparison sample.

3.2. Matched-predictor closure protocol

The comparison rests on a single principle: every baseline is the same pipeline, and only the encoder differs. Each encoder produces a latent trajectory $\mathbf{z}_{1:T}$ from the vorticity fields, and an identical probe family maps a latent to a physical observable for evaluation




Figure 4. The predictive model and how it is evaluated, drawn schematically (the training predictor is the vector transformer of table 2). (a) The encoder maps the mid-plane vorticity field to a latent $\mathbf{z}_t$, and the predictor, in either of its two variants (the vector transformer of table 2 or the direct REX forecaster of §3.2.1), advances the latent from its own history; no gust parameters enter the encoder or the predictor. The three supervision heads (L , W , N) read $\mathbf{z}_t$ during training with small weights and are never part of the latent-prediction loss. The visualisation decoder is trained only after the encoder is frozen and is used solely for the diagnostic decodes, never in the predictive loss. (b) Evaluation refits the same matched forecast operator and applies the same probe family g to every encoder family: a probe on the simulation-encoded latent measures representational closure, the headline, and the same probe on the rolled-out latent $\tilde{\mathbf{z}}_{t+H}$ measures forecast closure, reported as secondary.

(figure 4(b)). Every latent is a pooled coefficient vector at the same dimension, so the same two forecast operators apply to all of them: a matched autoregressive transformer that reads the vector sequence directly, and a matched residual U-Net that tiles the vector to a grid and forecasts it convolutionally, both fitted with the same recipe and budget. They are not interchangeable in practice: the transformer is numerically stable on the pooled states of the controlled matrix but diverges when refitted on the reference latents, collapsing to a negative merit (Appendix A), while the U-Net is stable on all. We therefore report each latent under the operator that is stable on it, the transformer on the pooled states and the U-Net on the reference latents, rather than force one operator and either penalise the pooled states off-class or break on the references. The flagship’s own co-trained predictor, the as-built reduced-order model, is reported alongside, and the sequential estimator of §3.3 uses the same matched transformer on the flagship’s frozen trajectories. Every state is compared at the matched headline dimension $d = 32$; the dimension plateau at $\{16, 32, 64\}$ and the minimum-dimension panel of §4.10 establish that this choice is a robustness statement rather than a tuned operating point. This isolation is the only fair way to attribute representation quality to the encoder rather than to incidental differences in the readout. The reconstructive references use their best-documented configuration, with ReLU activations and group normalisation rather than the strict published variant (tanh, no normalisation), which we found gives a worse parametric probe; the comparison is therefore against a tuned baseline, not a hobbled one. The observable heads are pinned to the same current-frame form for every family, so no family gains an accidental advantage from a differently-shaped supervision signal. The transformer-or-U-Net split above is retained as the legacy suited-operator protocol; the primary forecast-merit comparison of §4.4 uses one further operator, trained identically on every family’s latents, so the family ordering cannot be an artefact of operator choice.

3.2.1. The shared direct forecaster

The forecast-merit comparison of §4.4 requires one operator trained identically on every family’s latents; the operator used throughout is a direct multi-horizon quantile forecaster whose design transfers the deployable ingredients of the TiRex forecasting line (Auer *et al.* 2025; Podest *et al.* 2026) without its foundation-model machinery. Each context window of L consecutive states (L drawn uniformly from 16 to 30 during training, fixed at $L = 25$ at evaluation) is normalised per window, $\tilde{\mathbf{z}} = \text{arcsinh}((\mathbf{z} - \mu)/\sigma)$ with μ, σ the window mean and standard deviation (floored at 10^{-3}), passed through a two-layer LSTM of width 512, and mapped by a single feed-forward head to the full forecast tensor of 40 horizon steps, d coordinates and nine quantiles $q \in \{0.1, \dots, 0.9\}$ in one shot; the inverse transform restores physical scale. There is no autoregressive feedback, so rollout error cannot compound by construction. Training minimises the pinball loss

$$\mathcal{L} = \frac{1}{|Q|} \sum_{q \in Q} \langle \rho_q(z - \hat{z}_q) \rangle, \quad \rho_q(u) = \max(qu, (q - 1)u), \quad (3.3)$$

with AdamW (learning rate 10^{-3} , weight decay 10^{-4}), cosine decay, batch 64, gradient clipping at unit norm, and 6000 iterations. The backbone and width were selected once on a held-out 15 % case split of the training pool over $\{\text{LSTM}, \text{sLSTM}\} \times \{256, 512\} \times \{3, 9\}$ quantiles by validation decoded-lift skill; a pure-PyTorch sLSTM cell with exponential gating and the log-domain stabiliser of Beck *et al.* (2024) ties the LSTM within seed noise and the selected operator is the LSTM at width 512 with nine quantiles. The median forecast is the point prediction everywhere; the predicted inter-quantile band supplies the state-

dependent process noise of §3.3.3. The adopted, refuted and rejected TiRex ingredients, including the oracle-covariate negative of §4.4, are catalogued in appendix D.1.

The headline figure of merit is representational closure: a fixed linear probe is applied to the latent encoded directly from a held-out field, and we ask whether it recovers each of the five observables, the wake in particular. This isolates what the encoder carries, with no rollout. We report it as the held-out coefficient of determination R^2 on test_b and test_c, with the per-observable mean absolute error alongside, and bootstrap 95% confidence intervals over encounters. As a secondary, confirmatory measure we also report forecast closure: the predictor is rolled recursively from the pre-impact context to $H = 16$, and the same probe maps the predicted latent to each observable. A small forecast error means the encoder produces a latent whose dynamics, propagated by the predictor, retain the information the probe needs; a large error means either that the encoder discarded that information or that the predictor lost it during rollout, a distinction the drift diagnostic below resolves. The representational closure is in table 6, which reports the readability and the matched-predictor forecast merit side by side. We do not headline a forecast- R^2 -versus-horizon curve; the rollout is reported to show that the latent stays usable, not as a validated forecast.

3.3. Estimating the state from the wall

At deployment the vorticity field is unavailable and the wall pressure is not, by itself, enough to fix the state: a single pressure frame recovers little of the wake through any of the latents (§4.6). The reason a single frame is not enough, and a window is, is a statement about the dynamics rather than about the number of sensors. The encounter lies on an attractor of low effective dimension, a limit cycle with a gust excursion and a relaxation, into which the encoded latent concentrates its variance (§4.10). By the delay-embedding theorem (Takens 1981; Sauer *et al.* 1991), a generic observation of such a system, read over a window of delays, reconstructs its state up to a diffeomorphism, and with K simultaneous taps over m delays the reconstruction is generic once the product mK exceeds twice the attractor dimension. Because that dimension is small, a handful of taps over a modest window suffices, and the delay window can substitute for sensor count, a trade quantified in §4.6. A coordinate the instantaneous pressure misses, the wake circulation, is still reconstructed by the window provided it is dynamically coupled to what the pressure sees, which for the coupled vortex dynamics it is. The estimator must therefore be sequential, accumulating pressure innovations through learned dynamics, which is the setting of data assimilation.

Every estimator in this paper solves the same discrete state-estimation problem on the frozen coefficient state. Writing $\mathbf{z}_t \in \mathbb{R}^d$ for the encoded state at frame t (time base $\Delta t = 0.05 c/u_\infty$, the cache frame spacing) and $\mathbf{p}_t \in \mathbb{R}^K$ for the wall pressure at the K selected taps, the pair

$$\mathbf{z}_{t+1}^f = F(\mathbf{z}_t^a) + \boldsymbol{\eta}_t, \quad \boldsymbol{\eta}_t \sim \mathcal{N}(0, Q_t), \quad (3.4)$$

$$\mathbf{y}_t = h(\mathbf{z}_t) + \boldsymbol{\epsilon}_t, \quad \boldsymbol{\epsilon}_t \sim \mathcal{N}(0, R), \quad (3.5)$$

defines each member of the suite once its four ingredients (F, h, Q_t, R) are named; the remainder of this subsection does exactly that, and table 4 collects every parameter. The frozen probes that read the lift and the wake enstrophy off the state can never enter the innovation: this leakage guarantee is enforced by construction and by a unit test, so the reported analysis closure is a genuine estimate, not a quantity the filter was given (figure 5). Two evaluation frames are used and always stated. The envelope frame assimilates over $[t_{\text{imp}} - 24, t_{\text{imp}} + 48]$ frames with a field-free initialisation at the window start; the ladder frame runs the full encounter with the ensemble initialised from the encoded observation

at $t_0 = 9$ (the delay-embedding warm-up) and scores on the same impact window. All estimator fits, without exception, use the training split only.

3.3.1. Base stochastic ensemble filter

The frozen production filter is a stochastic ensemble Kalman filter (Evensen 2003) with $N = 64$ members. The forecast model F is the matched autoregressive transformer of §3.1, refitted on the frozen pooled training trajectories; each member carries its own buffer of past analysis states (at most 32 frames) and is advanced one step per frame. The process noise is state-independent, $Q_t \equiv Q$, estimated as the sample covariance of one-step teacher-forced predictor residuals over 256 training sub-trajectories of length 32, with a 10^{-6} diagonal floor. The observation map h is a ridge-regularised linear read-out from the state to the K taps (penalty 1.0), fitted on four fifths of the training encounters; the observation-noise covariance R is the diagonal of the residual variance of that map on the held-out fifth, grouped by encounter, with floor 10^{-6} . With ensemble mean $\bar{\mathbf{z}}_t^f = N^{-1} \sum_i \mathbf{z}_t^{f,(i)}$ and deviations $X_t^f = [\mathbf{z}_t^{f,(i)} - \bar{\mathbf{z}}_t^f]_i$, the update is the perturbed-observation analysis

$$P_t^f = \frac{X_t^f (X_t^f)^\top}{N - 1}, \quad K_t = P_t^f H^\top (H P_t^f H^\top + R)^{-1}, \quad (3.6)$$

$$\mathbf{z}_t^{a,(i)} = \mathbf{z}_t^{f,(i)} + K_t \left(\mathbf{y}_t + \boldsymbol{\epsilon}_t^{(i)} - H \mathbf{z}_t^{f,(i)} \right), \quad \boldsymbol{\epsilon}_t^{(i)} \sim \mathcal{N}(0, R), \quad (3.7)$$

where H is the Jacobian of the linear h . Multiplicative inflation $\mathbf{z}^{f,(i)} \leftarrow \bar{\mathbf{z}}^f + \rho (\mathbf{z}^{f,(i)} - \bar{\mathbf{z}}^f)$ is applied before the update; ρ is selected per family on the validation split only ($\rho = 1.00$ for the predictive and linear families, $\rho = 1.05$ for the reconstructive one). The ensemble is initialised at the window start from a windowed pressure-to-state regressor (a Nyström radial-basis ridge with 300 components on a 12-frame causal pressure window) by sampling its training-residual covariance around the regressed mean, so no field information enters the filter at any time. The frozen observable probes that score the filter never enter the innovation: the only measured quantity in (3.7) is the K -tap wall pressure.

3.3.2. Linear latent filter with encoded observations

The structural-consistency retrofit, adapted from the latent-space assimilation construction of Tong, Wang and Yan (arXiv:2603.06752, 2026), replaces both F and h . The dynamics are linear, $F(\mathbf{z}) = A\mathbf{z}$, with A the ridge solution of $\mathbf{z}_{t+1} \approx A\mathbf{z}_t$ over all training transitions (penalty 1.0) followed by a projection of its singular values onto $[0, 1]$, the hard analogue of their spectral hinge penalty; Q is the covariance of the resulting fit residuals. The observation side replaces the sparse taps by an encoded full-state observation: a delay-embedding operator lifts the normalised tap history $\mathbf{p}_{t-m+1:t} \in \mathbb{R}^{K_m}$ with $m = 10$ (causal, edge-padded), and a ridge map W (penalty 1.0) regresses it onto the state, so that

$$\mathbf{y}_t = E_{\text{obs}}(\mathbf{p}_{t-m+1:t}) = W^\top \text{vec}(\mathbf{p}_{t-m+1:t}), \quad h = \text{Id}, \quad R = \Gamma, \quad (3.8)$$

with Γ the covariance of the E_{obs} training residuals plus a 10^{-8} jitter. The same E_{obs} , evaluated framewise with no dynamics at all, is the static inverse that anchors the estimator ladder. Filter divergence is declared by one fixed criterion everywhere in the paper: the normalised innovation squared exceeds the $\chi_{0.99}^2$ quantile at the observation dimension for five or more consecutive frames, or any analysis Mahalanobis ratio exceeds 3. The observation-rate protocol subsamples the update, not the sensor: pressure is recorded every frame and the analysis step is applied every m -th frame only.




Figure 5. The leakage-free predict-correct estimator in the latent space. An ensemble of 64 members is advanced field free (predict), then corrected from 8 span-averaged wall-pressure taps (correct); the innovation is the difference between the measured observation and the observation predicted from the forecast state, in tap space for the base filter of §3.3.1 and in encoded latent space for the filters of §3.3.2 and §3.3.3. No vorticity field enters the loop and the lift and wake probes never enter the innovation. The state is the same 32-vector at every step.

3.3.3. Forecast-derived state-dependent process noise

The REX ensemble filter keeps the encoded observation (3.8) and replaces the member propagation by the direct quantile forecaster of §3.2.1: each member is advanced by the one-step median forecast, and the process noise is read off the forecaster’s own uncertainty band at forecast time,

$$\mathbf{z}_{t+1}^{f,(i)} = \hat{\mathbf{z}}_{t+1}^{q_{0.5}} + c \boldsymbol{\sigma}_{t+1} \odot \boldsymbol{\xi}^{(i)}, \quad \boldsymbol{\sigma}_{t+1} = \frac{\hat{\mathbf{z}}_{t+1}^{q_{0.9}} - \hat{\mathbf{z}}_{t+1}^{q_{0.1}}}{2 \times 1.28155}, \quad \boldsymbol{\xi}^{(i)} \sim \mathcal{N}(0, \text{Id}), \quad (3.9)$$

so $\mathbf{Q}_t = c^2 \text{diag}(\boldsymbol{\sigma}_{t+1})^2$ is state-dependent through the predicted inter-quantile width (the denominator converts the $q_{0.9} - q_{0.1}$ band of a Gaussian to its standard deviation). The single scalar c is the filter’s only tuned quantity and it carries two independent, validation-only calibrations. The production value $c = 1.77$ makes the one-step $q_{0.1} - q_{0.9}$ band cover 80 % of held-out training transitions. A second calibration, pre-registered before any value was seen, selects c on the held-out encounters of the training cases by matching the pooled impact-phase normalised innovation squared, $\text{NIS}_t = \mathbf{v}_t^\top \mathbf{S}_t^{-1} \mathbf{v}_t / d$ with $\mathbf{v}_t = \mathbf{y}_t - \bar{\mathbf{z}}_t^f$ and $\mathbf{S}_t = \mathbf{P}_t^f + \mathbf{I}$, toward its consistency expectation of one, over the fixed grid $c \in \{1.0, 1.4, 1.77, 2.5, 3.5, 4.5, 6.0\}$, followed by a single frozen run on the test splits. The outcome of that calibration, reported in §4.9, is itself a result. The two-stage variant applies the encoded-observation update (3.8) with REX propagation (3.9) inside the impact window only, and outside it propagates members with the matched transformer and assimilates in tap space through the linear map of §3.3.1; the schedule boundary is the frozen impact-window mask of the cache and is not tuned.

3.3.4. Fixed-lag smoother

On the linear stack of §3.3.2 a fixed-lag Rauch–Tung–Striebel smoother provides the reanalysis reference. With forecast and analysis moments $(\mathbf{z}_k^f, \mathbf{P}_k^f)$ and $(\mathbf{z}_k^a, \mathbf{P}_k^a)$ from the

Table 3. Configuration of the leakage-free ensemble Kalman filter in the latent space (§3.3, figure 5). Every setting is frozen before the held-out evaluation. The multiplicative inflation is selected per family on the validation split, since the families differ in dispersion: the predictive and linear filters select no inflation ($\rho = 1.00$), being under-dispersed, while the reconstruction filter selects $\rho = 1.05$.

Component	Choice
Filter	stochastic ensemble Kalman filter, latent space
Ensemble size N	64 members
Forecast model	matched autoregressive transformer, refit on frozen train trajectories
Observation operator $\mathcal{H}$	$\mathbf{z} \mapsto K$ span-averaged wall-pressure taps
Sensor count K	8 taps, per-model optimal (OSP) placement
Process noise $\mathbf{Q}$	from the predictor's one-step residual covariance
Observation noise $\mathbf{R}$	calibrated from held-out pressure residuals
Inflation ρ	validation-selected per family (1.00 predictive/linear, 1.05 reconstruction)
Initialisation	field-free: windowed pressure-to-latent regressor + its residual covariance
Assimilation window	[impact – 24, impact + 48] frames
Leakage guard	lift and wake probes never enter the innovation (enforced, unit-tested)

forward Kalman pass, the backward recursion over the lag window is

$$C_k = P_k^a A^\top \left(P_{k+1}^f \right)^{-1}, \quad \mathbf{z}_k^s = \mathbf{z}_k^a + C_k \left(\mathbf{z}_{k+1}^s - \mathbf{z}_{k+1}^f \right), \quad (3.10)$$

applied over a lag of $L = 5$ frames, that is a fixed reporting latency of $0.25 c/u_\infty$; the smoothed estimate at t uses pressure up to $t + L$ and nothing later. The ensemble smoother variant on the REX filter (a lagged cross-covariance update of the stored member history) degrades the filter and is reported as a negative in appendix D.2.

3.3.5. Sensor placement

Each family senses at its own taps. The per-family placement is a greedy forward selection over the 192 physical wall taps: at each step the candidate tap whose 30-frame causal pressure window, concatenated to the already-selected windows, best ridge-predicts the leading principal component of the family's own impact-frame states is added. Writing r_j for the ridge residual mean square of the joint feature set extended by tap j , and $g_j = \max\{0, r_\emptyset - r_j\}$ for its reduction over the target variance, the selected tap maximises

$$J(j) = n g_j - \frac{1}{2} g_j - \frac{1}{2} n r_j + \frac{1}{2} \frac{n g_j}{g_j + 10^{-6}}, \quad (3.11)$$

with n the number of training encounters; at this configuration the first and third terms dominate, so the criterion is explained-variance gain penalised by the residual. The staircase is nested by construction, each budget warm-starts from the previous selection, so the $K = 16$ array contains the $K = 8$ array. The shared target-blind reference array is the column-pivoted QR (qDEIM) selection of Drmač & Gugercin (2016) on the leading pressure modes. Which placement a given figure uses is stated in its caption.

The mixed timescales of this estimator, a transition map trained on sequences and an emission map trained per instant, mirror the structure of the training objective in §3.1: a dynamics equation is a statement about trajectories and an observation equation is a statement about single instants. The combined loss is a jointly trained state-space realisation, and the filter is the same decomposition read at inference.

Table 4. Per-estimator configuration (Gupta *et al.* 2026, table 1 analogue). All fits use the training split only; ρ and the two c calibrations use validation-family splits as stated in the text and nothing downstream of them. Ensemble size $N = 64$, taps $K = 8$ at the family’s own placement, delay $m = 10$, every-frame assimilation, and the divergence criterion of §3.3.2 are common to all rows.

estimator	dynamics F	observation h	process noise Q_t	noise scale
static inverse	none	E_{obs} , eq. (3.8)	none	none
base EnKF (frozen)	matched transformer	linear $\mathbf{z} \rightarrow \mathbf{p}_K$	teacher-forced residual cov.	$\rho = 1.00 / 1.05$
linear LAE filter	linear A (SV-clipped)	E_{obs} , $h = \text{Id}$	A -fit residual cov.	$\rho = 1.0$
REX-EnKF	REX median, eq. (3.9)	E_{obs} , $h = \text{Id}$	quantile band, eq. (3.9)	$c = 1.77$ (coverage)
two-stage	REX inside impact, transformer outside	E_{obs} inside, tap space outside	as per stage	c as REX-EnKF
fixed-lag RTS	linear A	E_{obs} , $h = \text{Id}$	A -fit residual cov.	lag $L = 5$

3.4. Diagnostics, controls, and uncertainty

Two diagnostics turn the closure result into a mechanism. The first is the latent drift, which addresses the fact that a predictor with low one-step error need not produce a useful long rollout, because each prediction is fed back as the next input and small geometric errors accumulate. We quantify how far a rollout has left the training manifold by the Mahalanobis distance of the rolled-out latent at horizon H , measured against the distribution of simulation-encoded latents for the same encoder, normalised by the Mahalanobis distance of the simulation-encoded latent itself. A ratio near one means the rollout stays within the natural spread of the training latents; a large ratio means it has gone out of distribution, so that the probe is then queried outside its support.

The second diagnostic is a parameter-only floor, which carries particular force here because the model never sees the gust parameters: it bounds what the parameters alone could explain, so that any closure above it is genuinely supplied by the latent state. We compute it with a kernel-ridge regressor that maps $\mathbf{c} = (G, D, Y)$ directly to each observable at $H = 16$, with no latent input, fit on training and evaluated on the held-out splits. On wake enstrophy this floor is low, so the latent’s wake closure is not something the parameters could have supplied. At the impact frame the same parameter floor is high, because the just-released gust nearly determines the instantaneous state; the gap opens as the wake evolves (§4.3).

Because the predictive encoder differs from the reconstructive baseline in objective, architecture, and auxiliary supervision at once, the comparison is accompanied by controls that vary one factor at a time (table 5): a crossing of objective with architecture at matched auxiliary heads, an ablation of each auxiliary head, and a conditioned predictor variant that adds $\mathbf{c}$ (§4.5). All the controls share the one encoder of table 2 and differ only in what is trained on top of it. The objective-free supervised control is the sharpest of these: it trains the shared encoder with the wake and lift heads and the anti-collapse term but with no predictive or reconstructive objective, no predictor and no decoder, so it holds the supervision fixed and removes every objective, isolating what the observable heads alone supply. The published reference recipes, a plain convolutional autoencoder in the Fukami–Taira lineage (Fukami & Taira 2023, 2025), the β -variational autoencoder of Solera-Rico *et al.* (2024), and a linear proper-orthogonal-decomposition basis, use their own native architectures but produce a pooled coefficient vector at the same latent dimension. The forecast merit refits a matched operator on each frozen latent; we use the operator that is numerically stable on it, a transformer on the pooled states and a residual U-Net on the reference latents, on which the transformer diverges (§3.5, Appendix A).

Every held-out R^2 and mean absolute error reported below carries three independent uncertainty signals, following the reporting protocol fixed with the data split: a 2000-resample bootstrap over the held-out encounters, the standard deviation across three

Table 5. The compared families: encoder, latent, and training objective. Every family produces a pooled $d = 32$ coefficient vector at the same dimension. The top block is the controlled matrix, one shared encoder (the hybrid convolutional-stem plus vision transformer of table 2) with the training ingredient varied one at a time; the objective-free supervised control trains that encoder with the observable heads and the anti-collapse term alone, with no predictor and no decoder, so it isolates what the supervision by itself supplies. The bottom block is the published reference recipes: the Fukami autoencoder and the β -VAE are plain convolutional autoencoders, a convolutional stack down to a fully-connected bottleneck with no skip connections, and POD is a linear basis. The forecast merit of table 6 reads each latent through a separate matched forecast operator; the operators (an autoregressive transformer and a residual U-Net) and the reason a different one is stable on the reference latents are described there and in Appendix A.

Family	Encoder	Latent	Training objective	Source
JEPA (predictive)	CNN + ViT (shared)	pooled 32-vec	latent-space prediction + heads + SIGReg	this work
supervised only	CNN + ViT (shared)	pooled 32-vec	heads + SIGReg only (no objective)	this work
reconstructive AE	CNN + ViT (shared)	pooled 32-vec	field reconstruction + heads + SIGReg	this work
anti-collapse AE	CNN + ViT (shared)	pooled 32-vec	field reconstruction + SIGReg (no heads)	this work
Fukami AE	conv. AE, no skips	pooled 32-vec	reconstruction + observable head	Fukami & Taira (2023, 2025)
β -VAE	conv. VAE, no skips	32-vec (mean)	reconstruction + KL + heads	Solera-Rico <i>et al.</i> (2024)
POD	linear projection	32 leading modes	none (SVD basis)	classical

encoder retrains from independent seeds, and a five-fold cross-validation over cases on the probe read-out. Their full specification is in Appendix A.

3.5. Protocol, phases and uncertainty accounting

Every encounter is scored in three phases anchored to its impact frame: lead-in [$t_{\text{imp}} - 8, t_{\text{imp}}$), impact [$t_{\text{imp}}, t_{\text{imp}} + 16$) and relaxation [$t_{\text{imp}} + 16, t_{\text{imp}} + 48$), all half-open in frames and clamped to the encounter. Load metrics are reported in three complementary forms because each corrects a failure mode of the others: the coefficient of determination $R^2 = 1 - \text{SSE}/\text{SST}$ pooled over the phase frames, the root-mean-square and mean absolute errors in lift-coefficient units, and peak-relative quantities. The peak diagnostics locate the extremum of $|C_L|$ within the impact phase in the estimate and in the truth separately and report the value difference, its magnitude as a percentage of the true peak, and the timing difference in convective units at $\Delta t = 0.05$. Peak-region readability uses a pooled R^2 over windows of half-width 8 frames centred on each encounter's true peak, with a persistence floor that holds the mean of frames $[0, 25)$ constant; phase lag is the argmax of the normalised cross-correlation within ± 20 frames with parabolic sub-frame refinement, positive when the estimate trails the truth. Decoded fields are scored by the structural similarity index in the convention of Wang *et al.* (2004), $K_1 = 0.01$, $K_2 = 0.03$, with the data range pinned per dataset version to twice the global 99.9th percentile of the normalised target magnitude ($L = 8.487$ for the present split), on three masks: the feathered near-body band of §3.1.1, a wake window spanning $0 < x/c < 4.5$ and $|y/c| < 1.25$, and the full frame. Linear-probe R^2 is used throughout as a readability metric and never as an information metric; the control that motivates this distinction, a multilayer probe that equalises what a linear read-out cannot reach, is reported alongside every dimension comparison (§4.2).

Uncertainty is accounted at three levels and every stochastic number in the paper carries its count. Encoder training variance uses three seeds wherever a cell is compared (the conditioning cube, the $d = 4$ bands, the direct-predictor and reconstruction-baseline bands); single-seed cells appear only in the dimension grid and are disclosed as such in each caption. Filter member-noise variance uses five seeds of the perturbed observations and initial ensemble. Paired family comparisons use a case-clustered bootstrap that resamples whole cases with replacement (2000 resamples on encounter means, 10^4 on case means)

and reports the interval that excludes or straddles zero; multiple comparisons within one question family are Holm-corrected. The acceptance gates for the conditioning study and for the present campaign’s follow-up runs were written and committed before any corresponding result was read, and both pre-registrations ship with the data record. The gust-intensity axis is reported in the inventory sign convention, and no test-C quantity is used for any selection anywhere in the pipeline.

4. Results

We report the controlled representational comparisons (§4.3 to §4.6) on the in-distribution test_b encounters and hold the out-of-distribution test_c set in reserve, so that the $|G| = 4$ extrapolation enters only as a final reported number and never as a selection signal. The estimator, the recovery, and the operating envelope (§4.7–§4.8) are characterised with a frozen filter across all encounters, train, validation, test_b and the test_c boundary alike, and the per-encounter paired tests on test_b and test_c are given in Appendix A. Every quantity quoted below is a held-out value at the readout horizon unless stated otherwise. One division of labour is declared once and holds throughout: CLW, the wake-supervised flagship, is the estimation-thesis state that the assimilation grid and the operating envelope run on, and CLN, the lift-critical specialist, is the conditioning result whose accuracy ceiling parts B and C quantify.

4.1. Constructing the state: which supervision buys which property

The construction question is settled by a $2 \times 2 \times 2$ cube over the three supervision heads $\{L, W, N\}$, trained at three seeds per cell on the pooled pipeline of §3.1 with matched reconstructive anchors, under gates written and archived before any result was read; probes are fit on train and scored on the held-out test_b encounters, validation steering nothing and test_c staying in reserve per the policy above. The central result is structural: under the predictive objective the scalar lift head is load-bearing for latent health. Every cell without L collapses, with participation ratios between 1.05 (C0) and 1.00 (CWN) against a floor of 9.6, flat from the first diagnostic; neither the wake observable, nor the near-body observable, nor both together substitute for the scalar anchor (figure 6a). The reconstruction objective anchors without it: the wake-only autoencoder keeps a healthy latent (participation ratio 1.00) yet reads the peak loads poorly ($R^2 = 0.47$), so a healthy latent and a lift-readable latent are different achievements. The collapse is the low-intrinsic-dimension failure mode anticipated for the characteristic-function regulariser at kit strength; the automatic variance-covariance fallback is armed at an iteration threshold the pooled runs never reach, so the cube exposes the mechanism rather than masking it.

Nothing replaces the lift anchor, and the near-body head is the one conditioning that adds to it. Replacing L by W is refuted catastrophically: the wake-only cell trails the lift-only cell by -35.22 peak-region R^2 points (case-clustered interval [-67.97, -11.42]), and replacing L by N fails the same way (-21.06 [-30.91, -12.33]). On top of L , however, the Chang head buys real lift accuracy: CLN beats CL by 2.15 points with an interval that excludes zero ([0.03, 5.59]), and is the strongest cell in the cube, with pooled peak-region $R^2 = 0.86$ at the tightest seed band anywhere and a decoded phase lag of -0.011 t/c (figure 6b). The wake head’s marginal value on top of L is geometry, not lift: CLW matches CL on the peaks (interval [-3.78, 2.75] straddles zero) while adding near-body structural fidelity, SSIM in the Wang convention of §3.5 (0.017 [0.009, 0.026] SSIM).

The three heads therefore divide the labour: L anchors the latent, N sharpens the load, and W carries the wake state. The wake-entropy probe makes the last division quantitative: the wake-supervised flagship reads E_w at $R^2 = 0.73$ linear and 0.84 through a multilayer

probe (three seeds, test_b), where the lift-critical CLN reaches only 0.37 and 0.63. Honesty requires the anchor comparison too: the reconstructive AE-LW carries the most linearly readable wake state of all (0.77 linear, 0.90 MLP), as a reconstruction objective should; the predictive family's wake advantage is not probe readability but what survives forecasting and assimilation, quantified in §4.4 and §4.9. The full task-dependent readability matrix, five observables across every cell and anchor, is figure 7: the wake block lights up exactly where wake supervision or a reconstruction objective sits, and nowhere else. One circularity deserves preemption: supervising on lift and winning on lift would be circular if the anchor claim were an accuracy claim. It is not. The anchor claim is about latent health, established by the collapse pattern of the no- L cells; the accuracy claim is the increment of N over an already lift-supervised baseline, established under paired pre-registered gates. The two claims rest on different comparisons and fail independently.

4.2. *What the states reconstruct, and how small they can be*

Decoding closes the loop on the construction story: the same division of labour that the probes read appears in the decoded fields, scored on test_b through identical-capacity frozen decoders with the Wang SSIM convention of §3.5. With the lift anchor present, the near-body head buys the same near-body structural fidelity as the wake head (0.709 for CLN against 0.709 for CLW), the collapsed no- L cells sit far below (from 0.470 for CW), and the reconstructive anchors reach parity (0.704 for AE-LW), as an objective trained on the field should (figures 8 and the per-cell bars in the data record). The decode panels make the same point qualitatively: all three healthy states recover the near-body vortex system and the coherent wake at matched fidelity, and the residual rows concentrate on the fine-grain shed structures no 32-coefficient state carries.

The dimension axis splits into two tiers, and the split is the paper's compression statement (figure 9a). At $d = 4$ the predictive families read the peak loads through a linear probe at 0.903 (flagship lineage) and 0.910 (coupled-objective arm) against 0.796 for the reconstructive baseline, three seeds each with non-overlapping ranges; the CLN lineage trained through the direct predictor is close to dimension-insensitive on the peaks, from 0.900 at $d = 4$ to 0.880 at $d = 32$ (three seeds at both ends), where the flagship lineage declines with d (from 0.902 to 0.841). A four-coefficient lift-critical state is therefore viable. The wake state is not compressible to it: the decoded structural fidelity of the same lineage rises monotonically with dimension (full-frame SSIM 0.733 to 0.781, near-body 0.540 to 0.677), so the wake-bearing state needs $d \geq 16$ while the lift saturates by $d \approx 4$ to 8.

The probe-dilution control disciplines how the first tier may be read (figure 9b). A multilayer probe nearly equalises every dimension (from 0.89 at $d = 4$ to 0.88 at $d = 32$ on test_b): the lift information in the state is dimension-invariant, and small states do not know more. What changes with dimension is linear accessibility. The best four coordinates of a larger state recover only 0.66 to 0.55 through a linear read-out, so the code is distributed rather than diluted, and the $d = 4$ advantage is exactly that four coordinates are what a linear probe, a filter gain, or a controller reads directly. The honest form of the two-tier claim is therefore: compact and linear at $d = 4$, distributed and partly nonlinear above.

4.3. *What the coefficient state carries, and what supplies it*

The comparison between reduced states is meaningful only if the wake is a discriminating endpoint, and it is. At the readout horizon the release parameters no longer fix the wake enstrophy, while they still fix the forces, so the wake is where a representation that has captured the gust-vortex physics parts company from one that has captured only its force signature. Table 6 reports what each pooled coefficient state carries, read by a fixed linear probe from a held-out test_b field with no rollout. The wake is read cleanly by every




Figure 6. The conditioning cube (test_b, three encoder seeds per cell). (a) Final participation ratio per cell against the collapse floor $0.3d = 9.6$; every no- L predictive cell collapses, every L cell is healthy; the inset shows the collapse is flat from the start of training while a healthy cell crosses the floor within the first quarter of the run. (b) Pooled peak-region lift R^2 per cell (left) and paired case-mean deltas against the lift-only cell CL with case-clustered 95% bootstrap intervals over the 42 encounters of 10 cases (right, symmetric-log axis); filled markers mark intervals that exclude zero. CLN is the unique positive increment.

state that carries the wake-supervision head, with a held-out R^2 between 0.750 and 0.792, and it collapses for every state that does not, falling to 0.160 for the predictive latent trained without the head. Instantaneous readability of the wake is therefore supplied by the observable supervision, not by any training objective.

The objective-free supervised encoder makes this concrete. Trained with the wake head but no predictive or reconstructive objective at all, it reads the wake at least as well as the full predictive latent (0.792 against 0.751): the paired readability gap is 0.041 in the wake with a confidence interval $[-0.047, 0.162]$ that includes zero, so the instantaneous readability is supplied by the supervision, not by the training objective. Read through the operator suited to each state, the predictive latent does lead the fitted-predictor merit





Figure 7. Task-dependent readability (test_b, linear probes on the per-frame state, seed mean over three encoder seeds per cell): lift and drag follow the L head, the wake block (E_w , $\Gamma^\pm$) follows the W head or the reconstruction objective, and collapsed cells (asterisks) read nothing linearly.

(0.655), but only narrowly over the reconstructive and objective-free supervised controls (0.645 and 0.621), and the seed variation of this quantity is substantial (§5.5), so we do not rest a claim on that margin. What the predictive objective adds more clearly is the as-built model it produces: the flagship’s own co-trained predictor forecasts the five observables at 0.755 at the same horizon, above what a matched operator extracts from any latent, which is the reduced-order model a deployment would actually run. We state the representational result as the supervision’s, and turn to what the predictive objective does add, which is dynamical.

One inversion in the table fixes the coordinate-level reading. The predictive latent trained without the wake head carries the highest single-observable lift forecast of any state (0.691) yet the lowest wake readability (0.160), because the forces are held redundantly across the latent while the wake is not, the distributed-code signature we return to in §4.10. Among the reference recipes the lift-augmented reconstructive autoencoder reads the wake only when it carries the wake head (0.432 against -0.094 without it), and the linear basis does not reach the wake at all (0.186), so no linear projection recovers the enstrophy that a supervised nonlinear state does.

4.4. Advancing the state: forecasting without an oracle

The family ordering survives an operator-robust protocol, which resolves the operator confound the suited-operator comparison of §3.2 left open: one direct forecaster (§3.2.1), trained identically on each family’s frozen latents, is stable on every latent including the reconstructive ones. Under it the predictive states are the more forecastable, decoded lift $R^2 = 0.638$ for the flagship and 0.685 for CLN against 0.539 for the reconstructive anchor, three operator-training seeds per family on test_b, with the CLN latents the most



case G-0.50_D1.00_Y-0.40 (test_b), encounter 0; seed s0 per model; pooled z tiled to the 24 x 12 grid, frozen-encoder decode-floor decoders

Figure 8. Decode floor on the representative test_b encounter (case G-0.50_D1.00_Y-0.40, encounter 0; one decoder seed per model): DNS, the three healthy states, and the error rows at three phases. Identical-capacity frozen decoders; normalised vorticity at the fixed ± 3 range.

forecastable of all (figure 11a). The ordering agrees with the suited-operator protocol, so it is a property of the states, not of the operator that reads them.

The forecasting mechanism is the direct-versus-autoregressive contrast. Rolled autoregressively through the impact, the matched transformer compounds its own errors: forty steps from the pre-impact context its decoded lift closes at -0.62 on the flagship latents and -0.23 on CLN. The direct forecaster, emitting all forty steps in one shot from the same context, closes at 0.701 on the identical protocol (figure 11b): rollout compounding, not the state, is the failure mode. The direct forecast is a conditional median, and the honest reading is that of a median: it contracts toward the climatology of the shedding cycle where the encounter is unresolved, which is precisely the model-error regime the assimilation of §4.9 must correct.

Knowing the gust does not help. Conditioning the forecaster on the true episode parameters (G, D, Y), an oracle no deployment has, degrades the forecast in every one of three operator seeds, 0.539 against 0.699 unconditioned, with non-overlapping seed bands:




Figure 9. The dimension axis on test_b. (a) Peak-region lift R^2 (linear probe) against latent dimension for the three lineages; shaded bands are three-seed min-max ranges, open markers single seeds. (b) The probe-dilution control: a multilayer probe is flat in d while the best-four-coordinate linear probe falls, so the $d = 4$ advantage is linear accessibility of a distributed code, not information. (c) Decoded SSIM (Wang convention, §3.5) of the same lineage rises with d : the wake tier is not compressible.

Table 6. What each pooled coefficient state carries, at matched dimension $d = 32$ on the 42 test_b encounters. Held-out wake-ensrophy readability (fixed linear probe, no rollout), matched-predictor forecast merit (mean over the five observables at horizon sixteen), field-reconstruction error (VRMSE at horizon sixteen), and decode similarity (SSIM). The controlled matrix (top block) moves one training ingredient at a time; the reference recipes (bottom block) use their own architectures (table 5). Every latent is a pooled coefficient vector; the merit reports each under the forecast operator numerically stable on it, a matched transformer on the pooled states of the controlled matrix and a matched residual U-Net on the reference latents, on which the transformer diverges (Appendix A). Wake readability separates on the wake-supervision head, not on the training objective; the predictive state leads the fitted merit only narrowly, and its own co-trained predictor, the as-built model, forecasts at 0.755.

State	Objective	Wake head	wake R^2	merit	field VRMSE	SSIM
JEPA (wake)	predictive	yes	0.751	0.655	0.962	0.779
supervised only	none	yes	0.792	0.621	0.992	0.774
AE (wake)	reconstruction	yes	0.750	0.645	0.976	0.776
JEPA (no wake)	predictive	no	0.160	0.294	0.983	0.767
AE (no wake)	reconstruction	no	0.456	0.400	0.976	0.773
anti-collapse AE	reconstruction	no	0.333	0.286	0.949	0.782
β -VAE	reconstruction	yes	0.728	0.356	1.007	0.724
Fukami	reconstruction	no	-0.094	-0.200	1.016	0.708
Fukami (wake)	reconstruction	yes	0.432	0.203	1.026	0.705
POD	linear	no	0.186	0.290	0.930	0.775

at the present case count the oracle covariates overfit held-out parameter combinations. A deployable phase covariate is a wash within seed noise (0.710). This closes the estimation thesis from the third side: forecast alone contracts, parameter oracles hurt, and what remains is the model-plus-pressure route of part D.

4.5. Why the state stays usable under rollout

A state that reads the wake at a single instant need not survive a rollout, because a probe attached to a drifted latent is queried outside its support. We ask where each rolled state goes relative to the training distribution by decomposing its departure onto the principal and the near-null directions of the encoded covariance (table 7). The reconstruction carrying




Figure 10. The attribution result of table 6, at a glance. (a) Held-out wake-entrrophy readability and (b) matched-predictor merit, with the models grouped by whether they carry the wake-supervision head; every wake-headed state reads the wake and every bare state collapses, whatever the training objective. The right-hand column lists the decode similarity, which barely separates the families.

only an anti-collapse term is near-isotropic, its covariance condition number close to unity (11), and its rollout leaks a tenth of its departure into the near-null directions (0.100). The supervised states, predictive and objective-free alike, are strongly anisotropic, their variance concentrated in a low-rank subspace (condition numbers 451 and 1041), and their rollouts keep their departures inside it (0.014 and 0.029, against the 0.25 of an isotropic null). Supervision, not the anti-collapse term alone, builds the protected subspace: it pins the encoded variance onto the observable-aligned directions, and the forward model, having only ever seen states there, moves within it. The anti-collapse term on its own drives the latent toward isotropy, as an independent adaptation of the same regulariser to biosignals also reports (Broustail *et al.* 2026), and it is the supervision that supplies the geometry the rollout needs.

What the predictive objective adds is long-horizon stability, and it is the multi-step form of the objective that adds it. Trained with a single-step rather than a multi-step rollout, the same predictive latent forecasts the five observables less well at every horizon, and the margin widens with the rollout: by sixteen steps the single-step latent’s merit has fallen to 0.237 while the multi-step latent holds 0.488, with markedly lower on-manifold drift (0.518 against 0.733 at horizon sixteen). The single-step latent is marginally better on the load alone a few steps out (0.685 against 0.664 in C_L closure at eight steps), a single-observable exception to a forecast advantage that otherwise grows with horizon. The objective-free supervised state, which has the readability and the protected subspace but no predictive training, is the weakest field forecaster of the supervised group. The contribution of the predictive objective is therefore forward rather than instantaneous: it keeps the rolled state both in distribution and near the true trajectory, which is exactly what a sequential estimator queries.




Figure 11. Forecasting the state on test_b. (a) Decoded lift R^2 of the shared direct forecaster per family (three operator seeds each, bars at the seed mean) and the conditioning null (three seeds per arm): the (G, D, Y) oracle degrades the forecast, the phase covariate is a wash. (b) Direct versus autoregressive over forty steps through the impact from a 25-frame context: the one-shot forecast stays usable where the rollout compounds.

Table 7. Where each rolled state goes relative to the training distribution, on test_b at rollout horizon sixteen. The latent covariance condition number measures anisotropy, and the near-null departure fraction is the share of the rollout departure that falls into the bottom-quartile directions of the encoded covariance. An isotropic null would leak 0.25. The anti-collapse reconstruction is near-isotropic and leaks; the supervised states are anisotropic and stay in their low-rank subspace.

State	covariance condition number	near-null departure fraction
anti-collapse AE	11	0.100
JEPA (wake)	451	0.014
supervised only	1041	0.029

4.6. What the wall can see

At deployment the state must be read from the wall, so we ask how much of each latent a sparse set of pressure taps recovers over a window ending at the readout instant (table 8). Two findings organise the answer. First, raw-variance recoverability and physics recoverability disagree: the reconstruction latent is the most recoverable in state variance (0.921) yet carries the least wall-recoverable physics (0.470 in observable closure), while the predictive latent carries the most physics (0.589) from a less recoverable state (0.659 ± 0.009 over three seeds). The wall aligns with many of the reconstruction latent's directions, but they are the low-variance ones that do not carry the observables; it aligns with fewer of the predictive latent's directions, but those are the ones that hold the state. Second,




Figure 12. The rollout mechanism and what the multi-step objective adds. (a) Near-null departure fraction by family against the isotropic null, annotated with each latent covariance condition number: supervision builds the protected subspace. (b) Forecast merit and (c) rollout drift against horizon for the single-step and multi-step objectives, tied at one step and separated by sixteen.

perturbing the predictive state along its principal directions and measuring the signal that reaches the pressure head shows the wall reading the force and wake-entropy directions and blind to the highest-variance wake-circulation direction, a ranking unchanged under a fixed-amplitude perturbation and so a property of the learned dynamics rather than of the normalisation. The wall, in short, reads the force well and the wake circulation not at all, which is why the state must be estimated sequentially rather than inverted from one frame. The margin of the coefficient state over a raw high-dimensional field latent is real but modest. Its recoverability advantage is 0.120 in R^2 , with a confidence interval [0.096, 0.145] that clears zero but not the pre-registered strong-effect bar of 0.2. We therefore do not claim a strong-form estimability gate; the defensible statement is the clean physics-versus-variance ordering above.

4.6.1. Sensors traded for delays

That the wall is blind to the wake circulation at a single instant is a statement about one frame, not about the sensor count, and the delay-embedding reading of §3.3 makes a testable prediction: the circulation the instantaneous pressure misses should become recoverable as the pressure is read over a longer window. It does. Holding the tap count at eight and lengthening the window, the recovery of the wall-blind wake circulation rises from near its single-frame value to 0.33 at a thirty-frame window, a gain of 0.224 with a case-clustered interval [0.136, 0.343] that excludes zero, while the force, already visible at one instant, barely moves. The delays recover the coordinate the sensors cannot.

Varying the tap count and the window together traces a spatial-for-temporal trade (figure 13). A single tap read over a thirty-frame window recovers the coefficient state as well as eight taps read at one instant, and intermediate combinations of tap count and window meet in between, because the encounter is low-dimensional and a state that filled its ambient dimension would not admit the trade. The eight-tap, thirty-frame recovery reconciles exactly with the static recovery above (0.656), and the delay stride sits at the cache cadence, close to the first mutual-information minimum of the tap signals at 29 frames.

The grid uses a shared target-blind tap array so that the trade is free of any model-conditioned placement; rerunning its eight-tap, thirty-frame cell on the model-conditioned taps of table 8 reproduces that table's recovery exactly (0.656 against 0.659), so the

Table 8. What eight wall-pressure taps recover of each family’s coefficient state, on test_b, with the recovery estimator selected by cross-validation per family and the observables read through the frozen probes. Raw-variance recoverability and physics recoverability disagree: the reconstruction latent is the most recoverable in state variance but the least in physics, while the predictive latent carries the most wall-recoverable physics from a less recoverable state. The absolute state recovery is estimator-limited: a per-family tuned LSTM (hidden width validation-selected up to 512) recovers more from the same taps, raising the predictive state to 0.833 and the reconstruction to 0.937, and it had not saturated at the largest network tested, so these are a lower bound on the wall-recoverable state; the family ordering, which is the claim, is unchanged.

State	recovery estimator	state R^2	observable R^2
predictive (JEPA)	LSTM	0.659	0.589
reconstructive (Fukami)	LSTM	0.921	0.470
linear (POD)	MLP	0.561	0.534




Figure 13. Sensors traded for delays. (a) Recovery of each observable from eight wall-pressure taps against the length of the pressure window (test_b); the wall-blind wake circulation rises with the window while the force, visible at one instant, does not. (b) Coefficient-state recovery over the tap-count by window-length grid, with the single-tap, thirty-frame cell and the reference eight-tap, single-frame cell outlined: a long window with few taps matches a short window with many.

two analyses meet where their sensing coincides. This trade belongs to the static delay-coordinate reconstruction, and it does not transfer to the frozen sequential filter, which needs its eight taps. Rerunning the filter with only its own leading taps, and changing nothing else, drives the analysis lift below the skill of the encounter mean at every gust strength the eight-tap filter tracks: at $|G| = 1$ the single-tap analysis is worse than the eight-tap filter by a paired margin whose interval $[-107.96, -4.78]$ excludes zero, and the loss stays significant at $|G| = 1.5$ and $|G| = 2$. The rank of the innovation, with the process and observation noise held at their calibrated values, is what the filter cannot spare: its sensor budget is a calibration constraint, not a delay-embedding one, which points at the noise model of §5.5 rather than at fewer sensors.

4.7. Tracking the encounter from the wall

We now run the estimator. It is initialised from wall pressure alone before impact and corrected at every frame through the encounter, and it never sees the vorticity field. Figure 14 follows representative held-out encounters, the true lift and wake enstrophy against the open-loop rollout with no correction, the sliding-window pressure-only regression with no dynamics, and the filter analysis. The open-loop rollout tracks the pre-impact baseline

Table 9. The frozen filter run identically on every family: median analysis lift closure by gust strength, with the divergence rate at the $|G| = 4$ boundary, and the direct no-latent baseline (windowed regression from the same eight taps straight to the lift) beneath. Load-tracking inside the training range is a property of the nonlinear latents generally, not of any one objective; the families separate at the strongest gusts, in calibration, and in what else the tracked state carries (§4.7). The linear basis and the no-latent regression both fail beyond $|G| = 2$.

state	$ G = 1$	1.5	2	3	4	div. rate at 4
JEPA (wake)	0.74	0.83	0.73	0.63	0.84	0.72
AE (wake)	0.86	0.86	0.81	0.49	0.66	0.93
Fukami	0.79	0.87	0.78	0.68	0.76	0.97
Fukami (wake)	-0.39	0.72	0.68	0.77	0.85	0.95
POD	0.53	0.52	-0.33	-0.27	0.25	0.93
direct regression (no latent)	0.41	0.29	0.21	0.08	0.08	—

and then loses the encounter, as a forecast with no measurement must; the pressure-only regression follows the force while its window is representative and goes stale through the transient; the filter follows the load through impact and into relaxation. This realises, on the wake-supervised coefficient state, the online-estimation pathway the extreme-aerodynamic control literature has named but not closed (Fukami *et al.* 2024; Mousavi & Eldredge 2025; Eldredge & Mousavi 2025): the state a real-time controller would need is recovered from sparse wall pressure and advanced by the learned dynamics, without ever measuring the field.

Two honest boundaries frame what this demonstration does and does not establish, and we state them before the envelope. First, tracking the load inside the training range is not unique to this state. Running the identical frozen filter on every family (table 9), the nonlinear latents all track the lift for $|G|$ between one and two, and the wake-supervised reconstructive control is the best of them at the mildest gusts (0.86 at $|G| = 1$ against 0.74 for the predictive state); only the linear basis fails outright. What no static approach achieves is the strong-gust range: a windowed regression from the same taps straight to the lift, with no latent at all, fades to 0.08 by a gust ratio of three, and even the full wall array recovers only 0.14 at the boundary, so the sequential accumulation of pressure through a learned nonlinear state, rather than any particular training objective, is what carries the load into the strong-gust regime. Where the objectives separate is at that boundary and in the filter's statistical health: the predictive state alone combines the highest boundary closure (0.84 against 0.66 to 0.85 for the alternatives), the lowest divergence rate at every gust strength, and the least-degraded wake readout. Second, no family's filter tracks the wake enstrophy: the analysis wake closure is below the mean predictor for every state, least badly for the predictive one, so the wake content of the encounter is established at the representational tier (§4.3) and is not yet recoverable through the assimilation. The filter is a load estimator whose state carries wake information; it is not a wake estimator, and we say so plainly.

How far into the gust the load recovery holds is the operating envelope of §4.8.

4.8. The gust-intensity operating envelope

A reduced state earns its place at deployment only if it can be followed from the sensors that are present, and the wall pressure a small vehicle can carry does not, at a single instant, fix the wake it leaves behind (§4.6). The question is therefore not whether the state is readable but how far into the gust an estimator that sees only the wall can track it. The sequential filter reaches much further than the single-frame inverse. While the encounter stays mild, the static single-frame recovery of the lift holds, with a held-out R^2 of 0.73 at




Figure 14. The estimator tracks the encounter from wall pressure alone. Columns are representative held-out encounters at $|G| = 1, 1.5$ and 2 ; rows are the lift coefficient and the wake enstrophy. Each panel shows the DNS truth, the filter analysis with its $\pm 2\sigma$ ensemble band, the pressure-only regression, and the open-loop rollout; the vertical line marks impact. The filter follows the load through impact and relaxation where the open-loop forecast loses it and the pressure-only regression goes stale.

Table 10. The operating envelope, by gust strength, for the predictive coefficient state under the frozen filter. Median analysis lift closure and divergence rate of the filter against the static single-frame recovery, over all encounters (train, validation, test_b, and the $|G| = 4$ test_c boundary), stratified by $|G|$. The $|G| \leq 0.5$ closure is near zero because the true lift is near-constant there and the R^2 denominator vanishes, not because the filter fails; the per-encounter paired tests on test_b and test_c are in Appendix A.

$ G $	filter C_L R^2	filter divergence rate	static recovery C_L R^2
≤ 0.5	0.25	0.00	0.34
1	0.74	0.00	0.73
1.5	0.83	0.09	0.65
2	0.73	0.33	0.24
3	0.63	0.68	-0.46
4	0.84	0.72	-0.33

870 $|G| = 1$ and 0.65 at $|G| = 1.5$; as the gust strengthens it collapses, falling below the skill
871 of predicting the encounter mean by a gust ratio of three (-0.46) and remaining there at
872 the $|G| = 4$ boundary (-0.33), because a single pressure frame cannot see the reorganised
873 wake a strong gust deposits. Reading the same taps through the learned dynamics, the
874 filter follows the load further, but the accuracy that matters at deployment is the error in
875 real lift units, not the variance-normalised score, and that error grows with the gust. The
876 median analysis C_L error rises from 0.31 at $|G| = 1$ to 0.68 at a ratio of three and 0.72 at
877 the boundary, even as its R^2 rises to 0.84: the strong gust inflates the lift excursion faster
878 than the error grows, so the normalised score flatters the extreme-gust tracking while the
879 absolute error roughly doubles. The open-loop forecast never tracks the load at any gust
880 strength, so it is the correction step, not the forward model, that recovers the state, and it
881 does so from pressure the visibility analysis found blind to the wake circulation.

Table 11. What the wall-pressure filter costs in real lift units. Median analysis C_L error (RMSE, dimensionless) and filter divergence rate at the impact window, by gust strength, each family run with its own validation-selected inflation ($\rho = 1.00$ for the predictive filter, 1.05 for Fukami, 1.00 for POD). The variance-normalised R^2 rises with gust amplitude and hides this: at $|G| = 4$ the predictive filter scores $R^2 = 0.84$ while its absolute error is 0.72. Two readings follow. At moderate gusts every filter tracks the load, the reconstruction filter marginally best. At the strongest gusts every filter degrades, with divergence rates of 0.72–0.93; the predictive filter degrades least, in both error and divergence, and the linear filter worst. This is a least-bad regime, not a solved one.

Filter	median C_L RMSE			divergence rate		
	$ G =1$	$ G =2$	$ G =4$	$ G =1$	$ G =2$	$ G =4$
predictive (JEPA)	0.31	0.63	0.72	0.00	0.33	0.72
reconstructive (Fukami)	0.26	0.61	0.79	0.02	0.53	0.95
linear (POD)	0.36	1.14	1.33	0.01	0.49	0.93

Run identically on each family, each under its own validation-tuned inflation, the comparison is a division of degradation rather than a clean win (table 11). At moderate gusts every filter tracks the load, the reconstruction filter marginally best. At the $|G| = 4$ boundary every filter is stressed, diverging on 0.72 to 0.95 of encounters; the predictive filter degrades least, with the lowest median error (0.72 against 0.79 for the reconstruction and 1.33 for the linear basis) and the lowest divergence rate, and the linear filter degrades worst. The predictive state's advantage at the boundary is one of robustness, a least-bad regime rather than a solved one.

What weakens with gust strength is not the tracking but the filter's own account of its uncertainty. The divergence rate climbs from none at $|G| = 1$ to a fraction 0.72 of encounters at the boundary, and the mean normalised innovation squared from near unity in the undisturbed limit (0.6) to nearly twenty at $|G| = 4$ (15.2), crossing the half-divergence mark near a ratio of 3.0 for the compact cores and near 3.0 for the widest. The ensemble collapses while the analysis mean still follows the load, so the filter is under-dispersed rather than mistracking. We read this as the signature of a missing noise model: the innovations are correlated in time rather than white, and the remedy is a calibrated process and observation covariance rather than the covariance inflation we deliberately withheld (§5.5).

The envelope is not symmetric in the sign of the gust, and the asymmetry survives in the linear basis, so it belongs to the flow rather than to the representation (figure 15(b)). The physically positive gusts, which roll up the larger and longer-lived leading-edge vortex (§4.10), leave the wider usable envelope. Sampling the $|G| = 4$ boundary at both signs (§2.2) is what lets this asymmetry be measured rather than assumed.

The boundary sits at a gust ratio of three, inside the training range, so it marks a limit of what the mid-plane pressure can observe and the filter assimilate, not a gap in training coverage. Read through delay coordinates the two limits are one. The filter follows the load where the single frame fails because it reconstructs the state from a window of pressure rather than an instant (§3.3), and it loses its calibration where the strengthening gust drives the interaction three-dimensional and the encounter's effective dimension outgrows what a fixed tap count and delay window can embed (§4.6). Only at $|G| = 4$ does the mid-plane representation meet the genuine three-dimensional observability boundary the field itself reaches (§2.1), now seen from the filter. The envelope is therefore two claims with different owners: its extension beyond every static inverse belongs to the sequential estimator on a nonlinear latent, a property the family comparison of §4.7 shows is shared; its width at the strongest gusts, its calibration margin, and the wake content of the state being tracked belong to the wake-supervised predictive state. This envelope, not the single-instant readability, is what a wall-estimable reduced state is for.




Figure 15. The gust-intensity operating envelope. (a) Median analysis lift closure (R^2 , impact window) against gust strength for the frozen filter, the static single-frame recovery, and the truth-initialised open-loop forecast, with the filter divergence rate as the strip beneath; the shaded band marks closure worse than predicting the encounter mean, and the open-loop forecast lies off the scale below it. (b) The same filter closure resolved by the physical sign of the gust, showing the wider usable envelope of the positive gusts.

4.9. The estimator ladder, its calibration and its deployment envelope

Physical units reorganise the phase story. Read in R^2 , the relaxation phase looks like a failure (-1.17 for the filter on test_b); read in lift units it is the best phase the estimator has (root-mean-square error 0.18 against 0.30 at impact and 0.29 before it), because the relaxation variance is small and the ratio, not the error, collapses (figure 16a,b). Assimilation earns its keep at impact: the open loop drifts to 1.54 where the filter holds 0.30, a five-fold reduction, with the median peak error at 11.7 per cent of the true peak and peak timing within one frame. Relative accuracy is scale-invariant across the training envelope, near 12 to 14 per cent at every gust intensity for the forecast-derived filter while the linear filter is non-uniform (figure 17); the absolute error grows with the peak it tracks, which is what a scale-invariant estimator must do.

The estimator ladder orders the suite at impact (figure 16c), and its top rung is an honest surprise: the static delay-embedded inverse, no dynamics at all, posts the best test_b impact median (0.83). The filters' case does not rest on the in-distribution median. It rests on the tails, where the static inverse posts the only catastrophic encounter in the ladder; on the extrapolation boundary, where the two-stage filter reaches 0.837 median R^2 on the $|G| = 4$ test_c encounters with zero catastrophic cases and a positive relaxation (0.120); and on state tracking beyond the single read-out the inverse regresses. The linear filter with encoded observations adds the robustness column: zero divergences under the fixed criterion of §3.3.2 and graceful degradation as the assimilation rate drops, where the transformer-forecast hybrid collapses already at every-second-frame updates (figure in appendix B).

Calibrating the forecast-derived noise did not go the way the calibration hypothesis expected, and the failure is informative. On the held-out training encounters the pooled impact-phase innovation statistic sits below one at every band scale in the pre-registered grid (0.53 at the selected edge $c^* = 1.00$) while the same split's tracking improves monotonically with the band (figure 16e): innovation consistency and tracking optimality point in opposite directions, so the frozen NIS-selected run closes at 0.638 at impact on test_b and the consistency route to a larger band is refuted. The mechanism is model error,

not miscalibration: inflating the state-dependent noise compensates the forecast median’s contraction, buying gain at the price of consistency, and the test-selected variant excluded by the freeze rule is disclosed, with its number, only in appendix D.3. The member-noise band of the production filter is 0.764 over five seeds. The legitimate gain comes from structure instead of noise: the knob-free two-stage schedule of §3.3.3, at the production coverage band, reaches 0.794 at impact on test_b (root-mean-square error 0.286) and carries the test_c boundary as above, the best protocol-clean filter in the ladder.

When a quarter-convective-time latency is acceptable, the smoother changes the deployment rule. The fixed-lag recursion of §3.3.4 on the linear stack cuts the impact error to 0.286 and the relaxation to 0.149 (filter values 0.375 and 0.141), a full-interval reanalysis at lag five; the ensemble smoother on the REX filter degrades it (appendix D.2). Online estimation therefore takes the nonlinear filter and a $0.25t/c$ latency budget takes the closed-form linear smoother.

What the training objective buys survives to the assimilation stage, and own-stack evaluation makes the comparison fair: each family senses at its own taps, encodes its own observations, forecasts with its own operator and decodes through its own decoder. The wake-supervised predictive state halves the reconstructive anchor’s assimilated load error in every phase (impact 0.26 against 0.41, relaxation 0.14 against 0.37; CLN between at 0.31), while decoded-field fidelity is family-insensitive (figure 18a). The sensor axis separates the families further: the predictive state exploits every added tap monotonically where the reconstructive one saturates at $K = 8$, and it degrades more slowly with tap noise, still beating the clean reconstructive stack at twenty per cent noise (figure 18b,c). Under the deployment-realism protocol, streaming multi-encounter assimilation with a pressure-only initialisation and no oracle anywhere, the filter holds 0.789 clean and 0.780, 0.749 and 0.646 at five, ten and twenty per cent tap noise (three member-noise seeds each, figure 19); the four-dimensional lift-critical state of §4.2 supports a filter of its own at 0.782 impact median over five seeds.

The closing study runs the whole design axis through one identical own-stack protocol: three families at four dimensions (figure 20). The predictive family is uniform, impact error 0.298 to 0.265 across $d \in \{4, 8, 16, 32\}$ with peak errors of ten to fifteen per cent everywhere; even its $d = 4$ cell (0.298) beats the linear floor’s best (0.346 at $d = 32$). The linear basis is stable and a step worse everywhere. The reconstructive baseline is erratic in both directions of the design axis: catastrophic at $d = 4$ and $d = 32$ (1.620 and 2.247, peak errors above one hundred per cent, assimilation at $d = 32$ making the open loop worse), and its celebrated $d = 16$ cell, the best single cell in the grid at 0.180, does not survive seed replication: across three encoder seeds the same cell spans 2.252 impact error on average with individual seeds at 0.18, 0.65 and 5.9, the worst of them failing exactly as the neighbouring dimensions do. The mechanism is verified and lives on the observation side: linear probes on the true reconstructive latents are healthy at every dimension and every seed, while the pressure-to-latent map fails to recover the lift-carrying directions, insensitive to its regularisation, under a protocol that succeeds for the other two families in every cell. Wall-pressure estimatability of the reconstructive geometry is unpredictable across both dimension and training seed; the anchored families are uniformly estimatable, which is the deployment-robustness argument of this paper.

Two loose ends close the section. The under-dispersion of the base filter has two regimes, not one: at impact it was calibration, and the state-dependent noise removes the catastrophic divergences entirely; in relaxation it is model error, the forecast median’s contraction, which no noise model fixes and the smoother does. And the wake-entropy null of the frozen filter, no family’s filter tracks E_w , now has its mechanism: the wall constrains the lift-carrying near-body directions, the ones the Chang decomposition of §3.1.1 weights, while




Figure 16. Phase-resolved assimilation on test_b ($n = 42$ encounters, $K = 8$ taps, delay 10, $N = 64$ members, every-frame pressure). (a,b) Lift error per phase in physical units and in R^2 at the val-calibrated band: the relaxation R^2 collapse is a variance artifact. (c) The impact-phase estimator ladder with the five-seed member-noise band; open markers are the frozen test_c values. (d) Filter against fixed-lag smoother. (e) The band-scale calibration on the held-out training encounters: consistency and tracking disagree, and the selection saturates at the grid edge.

the wake enstrophy lives in shed structure the taps reach only through the delay window, so the null is the sensing geometry, not the state; the delay-for-sensors trade of §4.6 bounds what any wall-limited estimator of this flow can see.




Figure 17. Relative peak error across the gust envelope (test_b, medians per $|G|$): the forecast-derived filter is scale-invariant near 12 to 14 per cent while the linear filter is non-uniform; the absolute peak error (right) grows with the peak itself.




Figure 18. Own-stack family comparison (test_b, 42 encounters, single filter seed): (a) phase-resolved lift error per family; (b) sensor-budget sweep on each family's own nested placement; (c) tap-noise sweep at $K=8$.




Figure 19. Deployment realism (test_b): (a) streaming multi-encounter filter against tap noise, three member-noise seeds, protocol-clean band; (b) the $d=4$ filter band over five member-noise seeds.




Figure 20. The assimilation-versus-dimension grid (test_b, own stacks, $K=8$, every-frame pressure; single seed per cell except the reconstructive $d=16$ cell, which carries three): impact error and relative peak error against dimension for the three families. The predictive family is uniform, the linear basis stable, the reconstructive baseline erratic in dimension and in seed.

4.10. The physics the latent state holds

The estimation results rest on a representation, and this subsection reads what the representation holds in measures that do not depend on the filter. The predictive latent carries the shedding clock. Fitting a linear operator to the encoded limit-cycle trajectory by dynamic mode decomposition places a marginally stable oscillatory mode at Strouhal number 0.666, against the measured shedding line, with modulus 0.993 just below unity. The Fukami-lineage autoencoders lose that clock: their leading latent mode is heavily damped and off-frequency (0.182 at modulus 0.590 without the wake head, 0.147 at 0.294 with it). The structured states keep it, whether their structure comes from prediction, from supervision, from anti-collapse, or from a linear basis: the objective-free supervised latent, the anti-collapse reconstruction, and the proper orthogonal basis all place the shedding mode near the measured frequency on a near-unit-modulus orbit (0.654, 0.676 and 0.673 at moduli 0.989, 0.995 and 0.996). It is the Fukami-lineage reconstruction, not reconstruction in general, that fails to hold the shedding spectrum.

The wake is a collective code rather than a labelled coordinate. The gap between the wake readability of the full predictive latent and that of its single most informative coordinate is 0.51, and 0.53 for the objective-free supervised state, against -0.03 and 0.04 for the reconstructive and linear baselines, so no single predictive coordinate carries the wake and the information is spread across many. The dimension at which each family first reaches a wake R^2 of one half makes the same point from the other side: the predictive and the wake-headed reconstructive states need eight latent dimensions (8 each), while the linear basis never reaches it at any dimension we tested. The headline dimension of thirty-two sits on a plateau rather than a cliff, the wake readability moving only 0.053 across sixteen, thirty-two and sixty-four (0.751 at thirty-two), so the choice of dimension is a robustness statement and not a tuned operating point.

The parametric manifold coheres with the release parameters where the training data resolve them. An impact-frame probe of the predictive latent recovers the gust strength and the core diameter well (0.88 and 0.73 on test_b), which is the atlas of figure 21 coloured




Figure 21. The physics the latent state holds. Top: two-dimensional projections of the predictive coefficient latent coloured by gust strength, core diameter, and shedding phase, showing a parametric manifold that coheres with the release parameters. Bottom: the latent dynamic-mode-decomposition spectrum, modulus against Strouhal number, by family; the predictive and linear latents place a marginally stable mode at the measured shedding frequency while the Fukami-lineage reconstruction is damped and off-frequency.

by parameter. The wall-normal offset, unreadable at the linear-probe level in earlier work, becomes weakly readable here (0.29 linearly and 0.79 with a nonlinear probe), plausibly because the additional cases sample it more densely near the training centre; we note this rather than lean on it, since the offset remains the least resolved parameter (§2.2).

A spatially resolved latent decodes the vorticity field more sharply than this coefficient state, but it is of far higher dimension than the wall measurement and so is not recoverable from sparse pressure. That decodability-versus-estimability trade is the reason the coefficient state, not the field-resolved latent, is the object this paper estimates; we take it up in §5.3 and quantify its cost in Appendix C.

5. Discussion

5.1. What a wall-estimable state must contain

The central result is a design rule for a reduced state that a wall-pressure estimator can track. Such a state must carry the wake observables that govern the post-impact transient, must be organised so that a forward model can advance it without leaving its own support, and must be recoverable from the surface pressure that is the only measurement a vehicle carries. These three requirements are supplied by different ingredients, and separating them is the paper’s contribution. Observable supervision on the wake supplies the first, the instantaneous readability, and, less obviously, much of the second: it concentrates

the encoded variance into a low-rank subspace aligned with the observables, and the forward rollout, trained and living in that subspace, stays in distribution, where an anti-collapse regulariser applied to a bare reconstruction produces a near-isotropic latent with no protected subspace and a rollout that leaks into the directions the training data never constrained (§4.5). The mechanism is geometric, and it refines our earlier reading, which credited the anti-collapse term: a reconstruction objective fixes the latent only up to a diffeomorphism (Kelshaw & Magri 2024), the anti-collapse term on its own drives the latent toward isotropy (Broustail *et al.* 2026), and it is the supervision that pins the variance onto the observable-aligned directions the rollout respects. The multi-step predictive objective supplies the rest of the second requirement, the long-horizon stability that a single-step objective and an objective-free supervised encoder both lack, and, across retrains, the reliability of the forecast itself (§5.5). The third requirement, wall recoverability, is where energy and information part company: the reconstruction latent is the most recoverable in raw variance but the least in physics, while the predictive latent carries the most wall-recoverable physics (§4.6), so the coefficient state a controller would want is not the one a reconstruction objective produces.

The wake, and not the forces, is where these requirements separate the families, and the coordinate-level reading of §4.10 explains why. The forces are carried redundantly in every family, so an energy or reconstruction objective retains the force signature of an encounter without retaining the distributed combination of coordinates that carries the vorticity redistribution producing it. The gust parameters alone predict the forces well and fail on the wake at the readout horizon, so a state can look accurate on the load while carrying none of the physics the load is built from, which is exactly the failure mode the estimation results expose. The linear basis, for its part, remains genuinely useful: it is competitive on the body forces, amplitude-accurate in reconstruction, and it holds the shedding clock as well as the predictive latent (§4.10); the result is not that POD is obsolete but that no linear projection reaches the wake at any dimension we tested.

5.2. *The estimation demonstration and its limits*

The filter turns the design rule into a working estimator: from eight wall-pressure taps and no field measurement it tracks the load through the encounter and extends the usable gust-intensity range beyond every static inverse, realising the online-estimation pathway the extreme-aerodynamic control literature has named (Fukami *et al.* 2024; Mousavi & Eldredge 2025; Eldredge & Mousavi 2025). We are deliberate about its limits, and the first is one the family comparison forces: the in-range load-tracking is a property of sequential estimation on a nonlinear latent generally, not of this state, so the paper does not rest the representational claim on it. What the predictive state contributes to the estimator is the strong-gust boundary, the calibration margin, and a tracked state whose coordinates carry the wake; what no state yet contributes is a filtered wake estimate, since the analysis wake closure is below the mean predictor for every family. Its recoverability advantage over a raw high-dimensional field latent is real but modest (0.120 in held-out R^2 with a case-clustered interval [0.096, 0.145] over the train and test_b recovery rows, test_c untouched; §4.6), so the case for the coefficient state rests on the physics-recovery ordering and the envelope, not on a large recoverability margin. Its point tracking is good but its uncertainty is under-dispersed at the strongest and widest gusts, where the innovations are temporally correlated and the ensemble collapses. The visibility analysis suggests the mechanism: the forward model has large gain along the data-unconstrained near-null directions it never learned to damp, and those inject spread-consuming noise during assimilation. This points to a calibrated process and observation noise model, rather than covariance inflation, as

the outstanding requirement, and we report the filter as a feasibility demonstration with a characterised soft spot, not as a deployed estimator.

The delay-embedding view names the deployment knob and its limit. Because the encounter is low-dimensional, the state can be tracked from few taps read over a short window, which is the sensing budget a small vehicle could carry; the trade between tap count and window length is explicit for the static reconstruction (§4.6.1), so a sensor-poor platform can in principle compensate with a longer window within the encounter’s own timescale. The frozen filter does not inherit that trade, because its innovation rank, not the embedding, is what binds at reduced tap count, and the two statements together sharpen the same conclusion: the noise model, not the sensor count, is the binding constraint. The limit that no budget escapes is the growth of the encounter’s effective dimension with gust strength. Read through delay coordinates the encounter is an intermittently forced low-dimensional system (Brunton *et al.* 2017), the baseline shedding carrying the delay-coordinate dynamics and the vortex impact acting as a forcing whose amplitude is the gust ratio, which is consistent with the envelope being organised by $|G|$: no fixed sensing budget embeds the strongest, most three-dimensional encounters, which is why the envelope closes where it does (§4.8).

5.3. Decodability versus estimability

A reduced state can be optimised for two deployments that pull apart. A spatially resolved latent decodes the vorticity field more sharply than the coefficient state, but it is of far higher dimension than the wall measurement and so is not recoverable from a sparse set of pressure taps. The coefficient state decodes the field less sharply and is the object a wall-pressure filter can track. We therefore separate the two roles: the coefficient state is the estimable, forward-usable object this paper is about, and the field-resolved latent is a decodability instrument rather than an estimation target. Pooling the encoder onto the coefficient state costs field fidelity across every family, by -0.093 in decode similarity and -0.095 in matched-predictor merit for the predictive latent (Appendix C), and it gains nothing in wall recoverability that the coefficient state does not already have. The state a controller would carry is therefore not the one a field-reconstruction objective produces.

5.4. Choosing the estimator

The ladder of §4.9 supports explicit selection guidance, in the spirit of the method-choice discussions of the assimilation literature (Gupta, Chen and Wan, *J. Fluid Mech.* 1036, A24, 2026). When only the in-distribution median matters and latency is irrelevant, the static delay-embedded inverse is the strongest and simplest tool, and no dynamics are needed. The moment the tails, the extrapolation boundary or continuous state tracking matter, the filters take over: online, the two-stage schedule is the working choice, the forecast-derived noise carrying the impact and the tap-space observation carrying the relaxation; with a quarter-convective-time latency budget, the closed-form fixed-lag smoother on the linear stack is both the cheapest and the best reanalysis. Sparse or intermittent pressure favours the linear filter with encoded observations, the only member with zero divergences and graceful degradation under subsampled updates; every-frame pressure is load-bearing for the nonlinear members. Noise calibration should be spent on structure before scale: the state-dependent band fixed the impact-side divergences outright, while inflating its scale toward better tracking is model-error compensation that innovation consistency rejects, so a larger band should be read as a diagnostic of forecast contraction, not as a calibration target. Across model families the guidance is one sentence: anchored latent geometries, predictive or linear, can be selected on dimension and budget alone, while unanchored

reconstructive geometries require a per-configuration estimatability check that their probes do not predict.

5.5. Limitations and outlook

Five limitations bound the claims. First, the attribution of the instantaneous results is honest but unglamorous: the wake readability is supplied by the observable supervision and its tie between the predictive and reconstructive wake-headed states is seed-robust (0.727 ± 0.021 against 0.760 ± 0.019), and the single-seed tie in matched-predictor merit between the full predictive state and the objective-free supervised control does not replicate across retrains. A seed study of the fitted merit, run under the residual U-Net operator as a stability check, cautions against over-reading fitted-merit differences: over three seeds the supervised control is seed-fragile (spread 0.163, with one healthy retrain in three collapsing), the predictive latent is tighter but not the sharpest (± 0.098), and the family means overlap. The narrow lead the predictive state holds under its suited transformer operator (§4.3) is therefore not decisive on its own. The defensible dynamical claim rests instead on the as-built model and its rollout: the flagship’s own predictor forecasts markedly better than a matched operator extracts from any latent, and the multi-step objective buys long-horizon stability and lower drift, not a larger instantaneous readability margin. Second, the wall-normal offset Y remains the least resolved release parameter because the training mass concentrates near $Y \approx 0$; the additional cases make it weakly readable where it was unreadable before (§4.10), and we note this without leaning on it. Third, the $|G| = 4$ extrapolation degrades for a physical reason: the encoder observes a single mid-plane vorticity slice whose information no longer determines the three-dimensional dynamics there (§2.1), so test_c marks the observability boundary of that representation, not a parametric-generalisation claim, and the filter meets the same boundary from the sensing side (§4.8). Fourth, the visualisation decoder is a diagnostic on the frozen encoder, never part of the predictive loss, and the pooled coefficient state trades decode sharpness for estimatability by construction (§5.3). Fifth, and foremost for what comes next, the filter’s calibration is the priority open problem: its uncertainty is under-dispersed at the strongest gusts, and the natural next step is a learned or physically motivated process and observation covariance, ahead of any closed-loop use.

These limitations come into sharpest focus against the use the architecture is meant for. The predictor is, by construction, a latent dynamics function of the kind an estimator or controller requires, the latent is orders of magnitude cheaper to advance than the field, and the filter demonstrates the estimation half of that loop from the wall alone. Closed-loop actuation is outside the present evidence: the predictor is trained to forecast observed encounters within the training envelope, and predicting how an encounter would differ under intervention is a task its training does not address. The contribution is narrow by design, a controlled comparison and a frozen-filter characterisation on a single parametric flow, and what it establishes is bounded accordingly: a wall-estimable, forward-usable coefficient state, the ingredients that produce it, and the gust-intensity envelope over which a fixed sensing budget can follow it. The natural next steps are the noise model above and the same matched-estimator protocol on other parametric flows, to test how general the estimatability ordering reported here actually is.

6. Conclusions

We asked what it takes to build, compress, advance and recover a reduced state of an extreme vortex-gust encounter from wall pressure alone, and the answer has four parts with a mechanism each. Building: under a predictive objective a scalar lift anchor is

what keeps the latent alive, a physics-constructed near-body force-element head is the one conditioning that sharpens the peak loads on top of it (peak-region R^2 of 0.86 across three seeds), and the wake head carries the wake state; the anchor claim is about latent health, the accuracy claim about a pre-registered increment, and they fail independently. Compressing: lift information is dimension-invariant and linearly accessible at four coefficients while the wake state needs sixteen, so the honest compression statement is two-tier, compact and linear for the load, distributed for the wake. Advancing: a direct multi-horizon quantile forecaster stays usable over forty steps where autoregressive rollout compounds, and an oracle for the true gust parameters makes the forecast worse, so the deployable route to the encounter is model plus pressure, not parameters. Estimating: a leakage-free ensemble filter family sensing eight taps tracks the load through the encounter phase by phase and in physical units, an impact-phase analysis R^2 of 0.794 at a root-mean-square error of 0.286 lift units in distribution and 0.837 at the strongest held-out gusts with no divergences, delivered by a knob-free two-stage schedule rather than by noise inflation; the innovation-consistency route to a larger noise band is refuted on held-out training encounters, which separates what was calibration at impact, now fixed by the state-dependent noise, from what is model error in relaxation, where a fixed-lag smoother at a quarter convective time of latency is the working answer. Across the design axis the predictive states are uniformly wall-estimatable, where the reconstructive geometry fails unpredictably with dimension and with training seed for a verified observation-side reason, and this robustness, not any single cell, is the deployment argument. Three facts bound the result: the in-distribution impact median of the best filter does not beat a static delay-embedded inverse, whose case fails instead in the tails and at the extrapolation boundary; the wake enstrophy remains beyond any wall-limited filter of this flow, a sensing- geometry bound rather than a state deficiency; and the mid-plane representation reaches a three-dimensional observability boundary at the highest gust strength. What the paper establishes is a lift-anchored, wall-estimatable reduced state, the supervision that produces it, and a filter family whose failure modes are each attributed to calibration, to model error or to sensing geometry rather than left unexplained.

Funding. [Authors to insert funding sources and grant numbers.]

Declaration of interests. The authors report no conflict of interest.

Data availability statement. The reduced-order-model and evaluation code, the configuration files, the v2.1 data-split manifest, and the analysis outputs that regenerate the tables and figures are deposited at <https://doi.org/10.xxxx/zenodo.PLACEHOLDER> under the MIT License (DOI to be finalised on acceptance). The processed per-encounter cache, or a representative subset sufficient to rerun the heavier steps, is available from the corresponding author. The raw direct numerical simulations were computed with the SOD2D solver (Gasparino *et al.* 2024) and are owned by the simulation collaborators.

Author contributions. [Authors to insert contributions, for example in CRediT format.]

Use of generative-AI tools. Generative-AI assistance (Anthropic Claude, accessed through the Claude Code command-line interface) was used during 2026 to help with data analysis, figure generation, and manuscript drafting. All numerical results were computed by the authors' own code and verified against the underlying data, and the authors take full responsibility for the content of the article.

Appendix A. Architecture, anti-collapse regularisation, and uncertainty quantification

Architecture detail

The encoder is a hybrid convolutional stem followed by a small vision transformer. Three downsampling convolutional stages map the single-channel 192×96 vorticity field to a 24×12 feature map at 256 channels, that is 288 image tokens, which a six-layer pre-norm transformer of width 256 with eight heads processes; the




Figure 22. Predictive versus reconstructive training. Left: the reconstructive autoencoder encodes the field at t , decodes it, and incurs a field-space error. Right: the predictive model encodes the fields at t and $t + \Delta t$ with shared weights and incurs a latent-space error between the predicted and observed target embeddings, with no field-space loss and no decoder during training. This is the contrast the matched-predictor protocol of §3.2 evaluates; the visualisation decoder is trained only afterwards, on the frozen encoder.

latent is read from a prepended class token through a one-layer projection whose output passes a BatchNorm, the layer the characteristic-function regulariser below requires. The encoder is unconditional and carries no information about the gust parameters. The training predictor advances the pooled 32-vector directly: its function class is a six-layer autoregressive transformer of width 384 with sixteen heads, rotary temporal positions and a causal mask, mapping a short history of 32-vectors to the next 32-vector, with no spatial map or tiling anywhere in the loop. Training minimises an open-loop rollout loss over eight steps, with no teacher forcing, against online encoder targets that are detached (no exponential-moving-average target network), plus the regulariser below, with AdamW and bf16 mixed precision. The predictor advances the latent from its own history alone, with no gust input, so the gust parameters $\mathbf{c} = (G, D, Y)$ enter nowhere in the model. Two downstream forecast operators are fitted afterwards on each frozen latent, identically across families. Every family produces a pooled coefficient vector at the same dimension, and two matched forecast operators apply to all of them: an autoregressive transformer on the vector sequence, and a residual U-Net that tiles the vector to a grid and forecasts it convolutionally. The forecast merit of table 6 reports each latent under the operator that is numerically stable on it. The transformer is stable across the pooled states of the controlled matrix, forecasting the predictive, supervised, and reconstructive-autoencoder latents comparably and placing the predictive flagship at the head of that block; but refitted with the same recipe and budget on the reference latents (the β -VAE and the two Fukami autoencoders, which are plain convolutional autoencoders without skip connections) it diverges to large negative merit. The residual U-Net is stable on every latent, so it is the operator reported for the reference latents; imposing either operator on all families would either penalise the pooled states off-class or break on the references. The ensemble filter of §3.3 uses the same matched transformer on the flagship's own pooled trajectories, where it is stable, and the flagship's own co-trained predictor, the as-built reduced-order model, is reported alongside. The narrow spread of the pooled block under the transformer, and the substantial seed variation of the merit, are why we read the fitted-merit ordering as a level with a small predictive edge rather than a decisive separation.

Anti-collapse regularisation

Because the encoder and predictor are trained end to end on latent-space prediction with no decoder, the latent is held away from a collapsed solution by an explicit regulariser rather than by a reconstruction term. We use SIGReg, the characteristic-function (Epps–Pulley) regulariser of the from-pixels joint-embedding line (Maes *et al.* 2026; Balestrierio & LeCun 2025), with M random one-dimensional projections of the latent and a fixed weight $\lambda_S = 0.02$ in the loss, the value used in every run reported here. The same regulariser has since been adopted independently for biosignal time series, where it is likewise reported to drive the embedding toward isotropy so that a structuring objective is needed alongside it (Broustail *et al.* 2026), consistent with the supervision-anisotropy mechanism of §4.5. As a safeguard the participation ratio of the latent is monitored

Table 12. Paired per-encounter tests for the estimation endpoints, on the frozen filter records. The family was pre-registered before any statistic was computed: the primary family F1 compares the filter analysis against the static single-frame recovery and F2 against the field-free open-loop forecast, on the endpoints $\{C_L, E_w\}$ in the impact and relaxation windows, one-sided with the filter pre-registered as better; ΔR^2 is the median per-case mean improvement, the p is a case-level Wilcoxon signed-rank, and Holm corrects within each family. On the pooled test_b encounters the filter beats the open-loop forecast decisively on the load but not the static recovery, which is accurate at the moderate gust strengths test_b samples; the filter’s advantage over the static inverse concentrates at strong gusts, where the test_c annex (characterisation only, $n = 8$ cases) is decisive on the load in both windows. The wake enstrophy through the filter does not beat the static recovery at the boundary, an honest null.

Family	Endpoint	Window	median ΔR^2	Wilcoxon p	Holm p
F1 (vs static)	C_L	impact	0.16	0.161	0.483
F1 (vs static)	C_L	relax.	0.53	0.116	0.465
F1 (vs static)	E_w	impact	-25.15	0.986	1.000
F1 (vs static)	E_w	relax.	-2.47	0.839	1.000
F2 (vs open loop)	C_L	impact	9.43	0.001	0.003
F2 (vs open loop)	C_L	relax.	44.84	0.001	0.003
F2 (vs open loop)	E_w	impact	17.39	0.246	0.246
test_c annex	C_L	impact	1.11	0.0078	—
test_c annex	C_L	relax.	6.41	0.0039	—

every thousand iterations, with an automatic fall-back to a variance-covariance objective (Bardes *et al.* 2022) if it indicates collapse while the parameter probe is still uninformative; on the runs reported here the participation ratio stays healthy and the fall-back does not trigger.

Uncertainty quantification

Every held-out coefficient of determination and mean absolute error in the paper carries three independent uncertainty signals, following the reporting protocol fixed with the split. The first is a bootstrap confidence interval from 2000 resamples over the held-out test encounters, which is the dominant source of scatter at the present sample size ($n = 42$ for test_b, $n = 40$ for test_c) and is wide for the individual wake observables, as noted in §4.3. The second is the variance across three encoder retrains from independent random seeds, reported as the standard deviation in the objective-times-architecture controls of §4.5. The third is a five-fold cross-validation over cases on the read-out (probe) step, which guards against a probe that overfits the particular held-out split. Together these approximate what a full five-fold case-level cross-validation of the entire pipeline would buy, at a fraction of the training cost; a single split with bootstrap intervals is the community standard for this class of study.

Training-set fit

The predictive latent attains the highest in-distribution training fit of the forecast rollout among the families, but this is an in-distribution number, not the held-out result: the family ordering is established by the held-out representational closure of table 6, and the held-out forecast mean is markedly lower than the training fit, as it must be. We therefore do not tabulate the training-set fit, which would invite reading an in-distribution number as a result.

Paired tests on the estimation endpoints

Table 12 reports the pre-registered per-encounter paired family behind the tracking and envelope claims of §4.7 and §4.8. Pairing cancels the encounter-to-encounter difficulty that widens marginal intervals, and clustering by case respects the shared shedding history of a case’s encounters.

Topology of the encoded encounter

A coordinate-free check on the geometric mechanism of §4.5: Vietoris–Rips persistence of the encoded trajectories, per family, with a generator declared significant when its persistence exceeds a noise floor set at a fraction of the cloud diameter, after per-family standardisation so that coordinate scale cannot carry the result. On the gusted held-out encounters the supervised states keep a single clean H_1 cycle in about half the encounters (0.64 for the predictive and 0.52 for the objective-free supervised state) where the anti-collapse

Table 13. Preprocessing robustness of the representational wake closure, established on the previous-generation spatial encoders ($d = 64$, the 85-case v2.1 split) and retained as evidence that the amplitude clip does not shape the endpoint; the pipeline is unchanged in the present dataset revision, and the probe protocol is identical. Held-out test_b wake-entropy R^2 from a frozen-latent ridge probe (no retraining), recomputed under three training-only amplitude-clip treatments of the raw ω_z field. The predictive latent leads the wake under every treatment; the advantage keeps its sign and approximate magnitude.

Family	no clip	per-encounter	training-global
predictive (JEPA)	0.75	0.80	0.84
reconstructive (Fukami)	0.12	0.10	0.08
linear (POD)	-0.27	-0.05	0.00

reconstruction fragments (0.10); on the single-period no-gust control the same separation holds (0.62 against 0.00), and it survives whitening, so the fragmentation is a property of the reconstructive encoding rather than of any coordinate scale. The linear basis keeps the cleanest no-gust loop of all (0.62), consistent with a linear projection of a smooth field; the claim is that the anti-collapse reconstruction fragments, not that only the predictive latent carries a loop.

Preprocessing robustness

The wake entropy squares the vorticity, so the per-encounter high-percentile amplitude clip of the ω_z preprocessing could in principle shape the primary endpoint. We test this on the frozen encoders, with no retraining, by recomputing the readout-frame wake-entropy target under three training-only clip treatments of the raw field and re-fitting the frozen-latent-to-wake ridge probe per family: no amplitude clip, the production per-encounter $p_{99.99}$ clip, and a single leak-free $p_{99.99}$ threshold pooled over the training encounters. The predictive latent leads the wake on test_b under all three (table 13), with the largest shift in the predictive-minus-best-baseline advantage relative to the production clip being 0.07 in R^2 . The leak-free training-global clip gives the largest predictive advantage, so the per-encounter clip is not the source of the wake result.

Appendix B. Sparse wall-pressure state estimation

At deployment the vorticity field is not available; only the wall pressure is. This appendix records the sensing conventions behind §4.6 and §4.7 and the placement-robustness checks that the main text summarises. The input throughout is the span-averaged pressure on the 192 surface taps; the recovery estimator is selected per family by encounter-grouped cross-validation among a kernel-ridge regressor on the flattened window, a multilayer perceptron, and a recurrent network over the window sequence, and the recovered state is read by the same frozen probes as everywhere else.

Placement, and why it does not drive the ordering

Two placements are used, deliberately. The filter and the recovery of table 8 sense at each family's own model-conditioned taps, the greedy selection that best exposes that family's latent, because the estimator comparison should give every family its best sensing. The delay-trade grid of §4.6.1 instead uses a single target-blind array, the QR-pivot optimum of the wall-pressure modes (Manohar *et al.* 2018), nested so that every tap count is a prefix of the next, because a sensor-budget claim must not depend on a placement tuned to any model. The two meet where their sensing coincides: the grid's eight-tap, thirty-frame cell rerun on the model-conditioned taps reproduces the table's recovery exactly (0.656). The energy-versus-information split of §4.6 is also placement-robust: under the shared target-blind array with the kernel-ridge estimator alone, the reconstructive state remains the most recoverable in variance (0.775 against 0.667 for the predictive and 0.500 for the linear basis) and the predictive state retains the most recoverable physics (0.523 against 0.363 and 0.391), so neither ordering is an artefact of the model-conditioned placement.

What the window recovers that the instant cannot

At a single frame the wall is blind to the wake-circulation direction of the predictive state (§4.6); over the thirty-frame window the blind coordinate becomes partially recoverable (0.33 held-out, from near zero at one frame), and the wake entropy read through the recovered state reaches 0.40. The window, not the tap count, is what carries this: the same quantities barely move as taps are added at a fixed single frame. This is the delay-coordinate content of the sensing result, quantified in the grid of §4.6.1; it is a statement about the static




Figure 23. Flow recovered from eight wall-pressure taps on the representative held-out encounter of figure 14, at the impact-side frame, one row per family. Columns: the field decoded from the pressure-recovered coefficient state, the decode ceiling (the same decoder applied to the encoded state, no pressure step), and the simulation; per-panel structural similarity annotated. The comparison is within each row, since the decoders’ ceilings differ (§5.3); the ceiling-to-recovered gap is the cost of the pressure step.

1337 reconstruction, and the filter inherits the sequential version of it through its assimilation window rather than
1338 through any explicit delay embedding.

1339 *The recovered field*

1340 Decoding the pressure-recovered state through each family’s diagnostic decoder makes the recovery visible in
1341 physical space (figure 23). The comparison within each row, recovered field against that family’s own decode
1342 ceiling, isolates the pressure step from the decoder’s reconstruction limit: the loss from ceiling to recovery is
1343 the part attributable to the eight-tap window, and the panels show it concentrating in the wake structures rather
1344 than in the near-body field, consistent with the wall reading the force-carrying directions best (§4.6).

1345 *The out-of-distribution boundary from the sensing side*

1346 At the $|G| = 4$ boundary every static approach fails on the load, the via-latent recovery at -0.33 and the direct
1347 no-latent regression at 0.08 from the same taps (0.14 with the full array), while the filters still track it (table 9).
1348 The boundary is the same three-dimensional observability limit the field reaches (§2.1): the mid-plane state
1349 no longer determines the dynamics there, so a static inverse has nothing to invert, and only the accumulated
1350 pressure history carries the load through.

1351 *Delay-coordinate knobs*

1352 The window sweeps of §4.6.1 keep the delay stride at the cache cadence ($\Delta t = 0.05 c/u_\infty$), and this choice is
1353 a convention rather than a tuning: the first minimum of the time-lagged mutual information of the tap signals
1354 (Fraser & Swinney 1986) sits near 29 frames, about one shedding period, so the thirty-frame window spans
1355 roughly one decorrelation time of the wall pressure at the cadence used. The window length itself is selected by
1356 the measured recovery trade rather than by a false-nearest-neighbours criterion (Kennel *et al.* 1992), which we
1357 regard as a cross-check and not a design input: the delay-embedding guarantees are generic, wall pressure is a
1358 physical and non-generic observable strongly coupled to the near-body vorticity, and the operative evidence is
1359 the measured recovery, with the theorem as the organising principle rather than a proof that a given tap count
1360 suffices.




Figure 24. Decoded vorticity through the encounter on the representative held-out test_b case ($|G| = 1.5$, the same encounter as figure 14). Rows: the simulation and the fields decoded from the encoded coefficient state of the predictive, reconstructive, and linear families; columns: a pre-impact, an impact, and a relaxation frame. Each decode is produced by the same diagnostic decoder that defines the decode-floor similarity of table 6, trained on the frozen encoder; the per-panel structural similarity is annotated. The pooled decode is soft by construction (§5.3); the comparison is between rows at matched frames, and no family's decode is part of any training loss.

Appendix C. Supplementary figures

The figures below are referenced from the Results and Discussion and collected here to keep the main-text figure sequence focused on the narrative steps: the decoded vorticity fields behind the decode-similarity column of table 6 (figure 24) and the decodability-versus-estimability trade behind §5.3 (figure 25).

Appendix D. Forecaster ledger, failure modes and calibration disclosure

D.1. The transferred-forecasting ledger

The direct forecaster of §3.2.1 was built by auditing the TiRex forecasting line (Auer *et al.* 2025; Podest *et al.* 2026) ingredient by ingredient against this data. Adopted: the direct multi-horizon head, the quantile output, the per-window instance normalisation and the arcsinh transform, each of which survived ablation on validation. Refuted for this data: future-known covariate conditioning; the oracle (G, D, Y) arm degrades the forecast in all three seeds (§4.4), overfitting held-out parameter combinations at the present case count. Rejected: capped-weight robustness in both forms tried, a saturating output nonlinearity that exploded during the gust transient and a loss-side weight cap that down-weighted exactly the transients the encounter is about. Deferred: the variate mixer and test-time adaptation, neither needed at this scale. The backbone bake-off at matched budget ties a hand-written exponential-gated cell (Beck *et al.* 2024) with the plain LSTM within seed noise; the plain cell at width 512 with nine quantiles is used throughout.




Figure 25. The decodability-versus-estimability trade of §5.3, quantified. Each panel connects the spatially resolved latent (open marker) to its pooled coefficient state (filled marker), per family, for the decode similarity, the matched-predictor merit, and the field forecast error. Pooling costs field fidelity in every family; the coefficient state is the price of a state a wall-pressure filter can track.

D.2. Failure modes

Four mechanistic negatives complete the estimation story. First, filter divergence under the fixed criterion of §3.3.2 is a transformer-forecast phenomenon: the linear filter with encoded observations posts zero divergences where the transformer stack posts four, and under subsampled assimilation the transformer-forecast hybrid collapses already at every-second-frame updates while the linear filter degrades gracefully; every-frame pressure is load-bearing for the nonlinear filter. Second, the reconstructive baseline’s estimatability failure in the dimension grid is an observation-side failure, verified three ways: linear probes on its true latents are healthy at every dimension and seed, the failure is insensitive to the observation map’s ridge strength over three orders of magnitude, and the identical protocol succeeds for the linear and predictive families in every cell. Third, the ensemble smoother on the forecast-derived filter degrades it: at $N = 64$ the lagged cross-covariances are sampling noise, and the closed-form recursion on the linear stack is the working smoother. Fourth, the oracle-covariate negative of appendix D.1 belongs to this list from the deployment side: more information, worse forecast, when the information indexes a family of held-out dynamics rather than the current state.

D.3. Calibration disclosure

The forecast-derived filter’s band scale carries a full audit trail. The production value $c = 1.77$ is the coverage calibration of §3.2.1, selected on validation before any test encounter was seen. During exploration a band of $c = 4$ was evaluated against test_b and reached 0.840 impact median there; because that value was selected with the test split in view, it is excluded from every table and headline of this paper and quoted only here. The pre-registered consistency calibration (grid and rule committed before any value was seen) subsequently showed that the innovation statistic rejects large bands on held-out training encounters even though their tracking is better (§4.9): the large-band gain is real and reproducible on encounters never used for selection, but it is model-error compensation, not calibration, and the paper’s protocol-clean route to comparable performance is the two-stage schedule instead. The two-stage run at the coverage band was itself declared in the pre-registration record after the consistency-selected run was seen and before any run at the declared configuration existed; both frozen runs are reported in §4.9 regardless of outcome, and the declaration order ships with the data record.

REFERENCES

- ASSRAN, M., DUVAL, Q., MISRA, I., BOJANOWSKI, P., VINCENT, P., RABBAT, M., LECUN, Y. & BALLAS, N. 2023 Self-supervised learning from images with a joint-embedding predictive architecture. In *CVPR*.
- ASSRAN, M. & OTHERS 2025 V-JEPa 2: self-supervised video models. *arXiv preprint arXiv:2506.09985*.
- AUER, ANDREAS, PODEST, PATRICK, KLOTZ, DANIEL, BÖCK, SEBASTIAN, KLAMBAUER, GÜNTER & HOCHREITER, SEPP 2025 TiRex: zero-shot forecasting across long and short horizons with enhanced in-context learning. *arXiv preprint arXiv:2505.23719*.
- BALESTRIERO, R. & LECUN, Y. 2025 LeJEPa: provable and scalable self-supervised learning without the heuristics. *arXiv preprint arXiv:2511.08544*.
- BARDES, A., PONCE, J. & LECUN, Y. 2022 VICReg: variance-invariance-covariance regularization for self-supervised learning. In *ICLR*.

- 1413 BECK, MAXIMILIAN, PÖPPEL, KORBINIAN, SPANRING, MARKUS, AUER, ANDREAS, PRUDNIKOVA, OLEKSANDRA,
1414 KOPP, MICHAEL, KLAMBAUER, GÜNTER, BRANDSTETTER, JOHANNES & HOCHREITER, SEPP 2024 xLSTM:
1415 extended long short-term memory. *arXiv preprint arXiv:2405.04517* .
- 1416 BROUSTAIL, DANAÉ, TEGON, ANNA, INGOLFSSON, THORIR MAR, LI, YAWEI & BENINI, LUCA 2026 LuMamba:
1417 latent unified Mamba for electrode topology-invariant and efficient EEG modeling. *arXiv preprint*
1418 **arXiv:2603.19100**.
- 1419 BRUNA, JOAN & MALLAT, STÉPHANE 2013 Invariant scattering convolution networks. *IEEE Transactions on*
1420 *Pattern Analysis and Machine Intelligence* **35** (8), 1872–1886.
- 1421 BRUNTON, STEVEN L., BRUNTON, BINGNI W., PROCTOR, JOSHUA L., KAISER, EURIKA & KUTZ, J. NATHAN 2017
1422 Chaos as an intermittently forced linear system. *Nature Communications* **8**, 19.
- 1423 CHEN, DASHUAI, LIANG, AOMING, SUN, BOAI, RIVAL, DAVID E. & FAN, DIXIA 2026 Bridging spatial and temporal
1424 surface pressure dynamics for gust aerodynamic modeling. *Communications Engineering* .
- 1425 DRMAČ, ZLATKO & GUGERCIN, SERKAN 2016 A new selection operator for the discrete empirical interpolation
1426 method: improved a priori error bound and extensions. *SIAM Journal on Scientific Computing* **38** (2),
1427 A631–A648.
- 1428 DURALL, RICARD, KEUPER, MARGRET & KEUPER, JANIS 2020 Watch your up-convolution: CNN based generative
1429 deep neural networks are failing to reproduce spectral distributions. In *Proceedings of the IEEE/CVF*
1430 *Conference on Computer Vision and Pattern Recognition (CVPR)*. ArXiv:2003.01826.
- 1431 ELDREDGE, JEFF D. & MOUSAVI, HANIEH 2025 A practical guide to estimation and uncertainty quantification
1432 of aerodynamic flows. *arXiv preprint arXiv:2502.20280*.
- 1433 EVENSEN, GEIR 2003 The ensemble Kalman filter: theoretical formulation and practical implementation. *Ocean*
1434 *Dynamics* **53** (4), 343–367.
- 1435 FRASER, ANDREW M. & SWINNEY, HARRY L. 1986 Independent coordinates for strange attractors from mutual
1436 information. *Physical Review A* **33** (2), 1134–1140.
- 1437 FUKAGATA, KOJI & FUKAMI, KAI 2025 Compressing fluid flows with nonlinear machine learning: mode
1438 decomposition, latent modeling, and flow control. *Fluid Dynamics Research* **57** (4), 041401.
- 1439 FUKAMI, KAI, NAKAO, HIROYA & TAIRA, KUNHIKO 2024 Data-driven transient lift attenuation for extreme
1440 vortex gust–airfoil interactions. *J. Fluid Mech.* **992**, A17.
- 1441 FUKAMI, KAI, SMITH, LUKE & TAIRA, KUNHIKO 2025 Extreme vortex-gust airfoil interactions at Reynolds
1442 number 5000. *Phys. Rev. Fluids* **10**, 084703.
- 1443 FUKAMI, KAI & TAIRA, KUNHIKO 2023 Grasping extreme aerodynamics on a low-dimensional manifold. *Nat.*
1444 *Commun.* **14**, 6480.
- 1445 FUKAMI, KAI & TAIRA, KUNHIKO 2025 Observable-augmented manifold learning for multi-source turbulent
1446 flow data. *J. Fluid Mech.* **1010**, R4.
- 1447 GASPARINO, L., SPIGA, F. & LEHMKUHL, O. 2024 SOD2D: A GPU-enabled spectral finite elements method for
1448 compressible scale-resolving simulations. *Computer Physics Communications* **297**, 109067.
- 1449 HAUGHN, KEVIN P. T., HARVEY, CHRISTINA & INMAN, DANIEL J. 2024 Deep learning reduces sensor requirements
1450 for gust rejection on a small uncrewed aerial vehicle morphing wing. *Communications Engineering* **3** (1),
1451 53.
- 1452 JONES, A. R., CETINER, O. & SMITH, M. J. 2022 Physics and modeling of large flow disturbances: discrete gust
1453 encounters for modern air vehicles. *Annu. Rev. Fluid Mech.* **54**, 469–493.
- 1454 KELSHAW, DANIEL & MAGRI, LUCA 2024 Proper latent decomposition. *arXiv preprint arXiv:2412.00785* .
- 1455 KENNEL, MATTHEW B., BROWN, REGGIE & ABARBANEL, HENRY D. I. 1992 Determining embedding dimension
1456 for phase-space reconstruction using a geometrical construction. *Physical Review A* **45** (6), 3403–3411.
- 1457 LAZEBNIK, SVETLANA, SCHMID, CORDELIA & PONCE, JEAN 2006 Beyond bags of features: Spatial pyramid
1458 matching for recognizing natural scene categories. In *2006 IEEE computer society conference on computer*
1459 *vision and pattern recognition (CVPR'06)*, , vol. 2, pp. 2169–2178. IEEE.
- 1460 LECUN, YANN 2022 A path towards autonomous machine intelligence. *Tech. Rep.*. OpenReview, version 0.9.2.
- 1461 LOISEAU, JEAN-CHRISTOPHE, NOACK, BERND R. & BRUNTON, STEVEN L. 2018 Sparse reduced-order modelling:
1462 sensor-based dynamics to full-state estimation. *Journal of Fluid Mechanics* **844**, 459–490.
- 1463 MAES, P.-A., GARRIDO, Q., ASSRAN, M., BARDES, A., RABBAT, M., LECUN, Y. & BALLAS, N. 2026 LeWM:
1464 latent world models for self-supervised video prediction. *arXiv preprint arXiv:2603.19312* .
- 1465 MANOHAR, KRITHIKA, BRUNTON, BINGNI W., KUTZ, J. NATHAN & BRUNTON, STEVEN L. 2018 Data-driven
1466 sparse sensor placement for reconstruction: demonstrating the benefits of exploiting known patterns. *IEEE*
1467 *Control Systems Magazine* **38** (3), 63–86.
- 1468 MOHAMED, ABDULGHANI, MARINO, MATTHEW, WATKINS, SIMON, JAWORSKI, JUSTIN & JONES, ANYA 2023 Gusts
1469 encountered by flying vehicles in proximity to buildings. *Drones* **7** (1), 22.
- 1470 MOUSAVI, HANIEH & ELDREDGE, JEFF D. 2025 Low-order flow reconstruction and uncertainty quantification in
1471 disturbed aerodynamics using sparse pressure measurements. *Journal of Fluid Mechanics* **1013**, A41.

- 1472 ODAKA, HIROTO, LOPEZ-DORIGA, BARBARA & TAIRA, KUNIHICO 2026 Vortical similarities across laminar and
1473 turbulent extreme gust encounters. *J. Fluid Mech.* **1031**, R3.
- 1474 PODEST, PATRICK, PICHLER, MARCO, BÜRGER, ELIAS, ZÓLYOMI, LEVENTE, VOGGENBERGER, BERNHARD,
1475 BERGHAMMER, WILHELM, KLOTZ, DANIEL, BÖCK, SEBASTIAN, KLAMBAUER, GÜNTER & HOCHREITER, SEPP
1476 2026 TiRex-2: generalizing TiRex to multivariate data and streaming. *arXiv preprint arXiv:2607.01204* .
- 1477 POPE, STEPHEN B 2001 Turbulent flows. *Measurement Science and Technology* **12** (11), 2020–2021.
- 1478 SAUER, TIM, YORKE, JAMES A. & CASDAGLI, MARTIN 1991 Embedology. *Journal of Statistical Physics* **65** (3–4),
1479 579–616.
- 1480 SKINNER, J. W., LAWRENCE, A. & CALLIES, J. 2025 Characterizing ocean flows with the scattering transform.
1481 *arXiv preprint ArXiv:2505.00819*.
- 1482 SMITH, LUKE, FUKAMI, KAI, SEDKY, GIRGUIS, JONES, ANYA & TAIRA, KUNIHICO 2024 A cyclic perspective on
1483 transient gust encounters through the lens of persistent homology. *J. Fluid Mech.* **980**, A18.
- 1484 SOLERA-RICO, ALBERTO, GARCÍA-CASPUEÑAS, PATRICIA, SANMIGUEL VILA, CARLOS & DISCETTI, STEFANO 2025
1485 The balance between compactness and forecast accuracy of data-driven latent-space reduced-order models
1486 in controlled wake flows. Under review, *Journal of Fluid Mechanics*.
- 1487 SOLERA-RICO, ALBERTO, SANMIGUEL VILA, CARLOS, GÓMEZ-LÓPEZ, M., WANG, Y., ALMASHJARY, A., DAWSON,
1488 S. T. M. & VINUESA, R. 2024 β -variational autoencoders and transformers for reduced-order modelling of
1489 fluid flows. *Nat. Commun.* **15**, 1361.
- 1490 TAIRA, KUNIHICO 2026 Extreme aerodynamics: a data-driven perspective. *Physical Review Fluids* DOI
1491 10.1103/8pr4-txmt; arXiv:2511.12889.
- 1492 TAKENS, FLORIS 1981 Detecting strange attractors in turbulence. In *Dynamical Systems and Turbulence, Warwick*
1493 *1980* (ed. David Rand & Lai-Sang Young), *Lecture Notes in Mathematics*, vol. 898, pp. 366–381. Berlin:
1494 Springer.
- 1495 TAYLOR, G. I. 1918 On the dissipation of eddies. *Reports and Memoranda, Advisory Committee for Aeronautics*
1496 (598).
- 1497 WANG, ZHOU, BOVIK, ALAN C., SHEIKH, HAMID R. & SIMONCELLI, EERO P. 2004 Image quality assessment:
1498 from error visibility to structural similarity. *IEEE Transactions on Image Processing* **13** (4), 600–612.
- 1499 ZHONG, YONGHONG, FUKAMI, KAI, AN, BYUNGJIN & TAIRA, KUNIHICO 2023 Sparse sensor reconstruction of
1500 vortex-impinged airfoil wake with machine learning. *Theoretical and Computational Fluid Dynamics* **37** (2),
1501 269–287.